| | | | | | ST. DEPARTMENT DIVISION O | OF NA | | | | | AME | FC NDED REPC | DRM 3 | | | |
|------------|------------------------------|--------------------------|------------------------|--------|---------------------------------|----------|----------------------|---------|------------------------|---|----------|-----------------------|---------|--------------|--|--|
| | | APP | LICATION F | OR | PERMIT TO DRILL | - | | | | 1. WELL NAME and | | R 21-30J1CS | | | | |
| 2. TYPE (| | RILL NEW WELL (| REENTE | R P&A | A WELL DEEPE | N WELL | . 🗅 | | | 3. FIELD OR WILD | | L BUTTES | | | | |
| 4. TYPE (| | | | | ed Methane Well: NO | | | | | 5. UNIT or COMMU | JNITIZA | TION AGE | EEMENT | NAME | | |
| 6. NAME | OF OPERATOR | ર | | | | | | | | 7. OPERATOR PHO | NE | L BUTTES | | | | |
| 8. ADDRI | SS OF OPERA | TOR | | | AS ONSHORE, L.P. | | | | | 9. OPERATOR E-M | AIL | 29-6515 | | | | |
| | RAL LEASE N | UMBER | 7.0. вох 1737. | | 11. MINERAL OWNE | RSHIP | | | | 12. SURFACE OW | | @anadarko | o.com | | | |
| | L, INDIAN, OF | ML 22793 OWNER (if box : | 12 - 'foo') | | FEDERAL IND | IAN |) STATE ([|) F | FEE 🔵 | FEDERAL IN | IDIAN (_ | STAT | | FEE () | | |
| | RESS OF SURF | | 16. SURFACE OWI | | | | | | | | | | | | | |
| 15. ADDI | CESS OF SUKF | ACE OWNER (II D | 10X 12 = 1ee | | 18. INTEND TO COM | MING | E BRODUST | TON F | DOM | 19. SLANT | VEK E-MI | ATE (II DO | (12 - 1 | | | |
| | AN ALLOTTEE 2 = 'INDIAN') | OR TRIBE NAME | | | MULTIPLE FORMATI | ONS | | | _ | _ | | | | 🔿 | | |
| | | | | | | | ling Applicati | | NO 📦 | | IRECTION | | HORIZON | | | |
| 20. LOC | | - | | OTAGES | | R-QTR | SE | ECTION | | - | ANGE | ME | RIDIAN | | | |
| | ON AT SURFAC | | _ | | SL 973 FEL | | SESE | | 30 | 10.0 S 10.0 S | | 1.0 E | +- | S | | |
| At Total | ppermost Pro | ducing Zone | | | L 1828 FEL L 1828 FEL | | NWSE NWSE | | 30 | 10.0 S | - | 1.0 E | - | S S | | |
| 21. COUN | | | 21 | | | | ST LEASE LINE (Feet) | | 23. NUMBER OF ACRES IN | | | | | | | |
| | | UINTAH | | | 25. DISTANCE TO N | 18 | 328 | | | | 6 | 44 | | | | |
| | | | | | (Applied For Drilling | g or Cor | | | | | | | | | | |
| 27. ELEV | ATION - GROU | JND LEVEL 5251 | | | | | | | | 29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE Permit #43-8496 | | | | | | |
| | | | | | Hole, Casing, | and Co | ement Info | ormat | tion | | | | | | | |
| String | Hole Size | Casing Size | Length 0 - 2080 | | ight Grade & Th | | Max Mu | | | Cement | | Sacks 180 | | | | |
| Surf | 11 | 8.625 | 0 - 2080 | 20 | 5.0 J-55 LTG | XC | 0.2 | | - | Type V Class G | | 270 | 1.15 | 15.8 15.8 | | |
| Prod | 7.875 | 4.5 | 0 - 9660 | 11 | 1.6 I-80 Butt | ress | 12. | 5 | Prem | nium Lite High Str | ength | 270 | 3.38 | 11.0 | | |
| | | | | | | | | | | 50/50 Poz | | 1140 | 1.31 | 14.3 | | |
| | | | | | ΑΊ | ГТАСН | MENTS | | | | | | | | | |
| | VERIFY T | HE FOLLOWIN | G ARE ATT | ACHE | ED IN ACCORDAN | CE WI | TH THE UT | ган о | OIL AND G | GAS CONSERVAT | ION GE | NERAL I | RULES | | | |
| ⊮ w | ELL PLAT OR | MAP PREPARED E | BY LICENSED | SUR | VEYOR OR ENGINEER | R | № сом | PLETE | DRILLING | PLAN | | | | | | |
| AF | FIDAVIT OF S | TATUS OF SURFA | ACE OWNER A | GREE | EMENT (IF FEE SURF | ACE) | FORM | 1 5. IF | OPERATO | R IS OTHER THAN | THE LEAS | SE OWNE | ₹ | | | |
| DI DRILLED | | URVEY PLAN (IF | DIRECTIONA | LLY | OR HORIZONTALLY | | торо | GRAPI | HICAL MAI | • | | | | | | |
| NAME D | anielle Piernot | | | TIT | TLE Regulatory Analyst | t | | P | PHONE 720 | 929-6156 | | | | | | |
| SIGNAT | URE | | | DA | TE 03/11/2011 | | | E | EMAIL dani | elle.piernot@anadark | co.com | | | | | |
| | ивек assign)4751537(| | | АР | PROVAL | | | | Bol | 20 Gill | | | | | | |
| | | | | | | | | | Pern | nit Manager | | | | | | |

NBU 1021-30P Pad Drilling Program
1 of 7

Kerr-McGee Oil & Gas Onshore. L.P.

NBU 1021-30J1CS

 Surface:
 1209 FSL / 973 FEL
 SESE

 BHL:
 2162 FSL / 1828 FEL
 NWSE

Section 30 T10S R21E

Unitah County, Utah Mineral Lease: ST UT ML 22793

ONSHORE ORDER NO. 1

DRILLING PROGRAM

Estimated Tops of Important Geologic Markers: Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:

| <u>Formation</u> | <u>Depth</u> | <u>Resource</u> |
|------------------|--------------|-----------------|
| Uinta | 0 - Surface | |
| Green River | 1048 | |
| Birds Nest | 1279 | Water |
| Mahogany | 1632 | Water |
| Wasatch | 4237 | Gas |
| Mesaverde | 7181 | Gas |
| MVU2 | 8163 | Gas |
| MVL1 | 8708 | Gas |
| TVD | 9423 | |
| TD | 9660 | |

3. <u>Pressure Control Equipment</u> (Schematic Attached)

Please refer to the attached Drilling Program

4. **Proposed Casing & Cementing Program:**

Please refer to the attached Drilling Program

5. <u>Drilling Fluids Program:</u>

Please refer to the attached Drilling Program

6. <u>Evaluation Program</u>:

Please refer to the attached Drilling Program

NBU 1021-30P Pad Drilling Program 2 of 7

7. Abnormal Conditions:

Maximum anticipated bottom hole pressure calculated at 9423' TVD, approximately equals 6,219 psi 0.64 psi/ft = actual bottomhole gradient

Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD

Maximum anticipated surface pressure equals approximately 3,944 psi (bottom hole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot, per Onshore Order No. 2).

Per Onshore Order No. 2 - Max Anticipated Surf. Press.(MASP) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

8. Anticipated Starting Dates:

Drilling is planned to commence immediately upon approval of this application.

9. Variances:

Please refer to the attached Drilling Program. Onshore Order #2 – Air Drilling Variance

Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2

- · Blowout Prevention Equipment (BOPE) requirements;
- · Mud program requirements; and
- · Special drilling operation (surface equipment placement) requirements associated with air drilling.

This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.

The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.

More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.

Background

In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.

NBU 1021-30P Pad

Drilling Program 3 of 7

Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.

The air rig is then mobilized to drill the surface casing hole by drilling a 11 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 11 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 8-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.

KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.

Variance for BOPE Requirements

The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.

Variance for Mud Material Requirements

Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.

Variance for Special Drilling Operation (surface equipment placement) Requirements

Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.

Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.

Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and

NBU 1021-30P Pad Drilling Program
4 of 7

on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line

Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.

Conclusion

The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.


10. <u>Other Information:</u>

Please refer to the attached Drilling Program.



KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

COMPANY NAME KERR-McGEE OIL & GAS ONSHORE LP DATE February 10, 2011 NBU 1021-30J1CS WELL NAME 9,423' TVD 9,660' MD FINISHED ELEVATION 5250.9 FIELD Natural Buttes **COUNTY** Uintah STATE Utah SURFACE LOCATION SESE 1209 FSL 973 FEL Sec 30 T 10S R 21E Latitude: 39.91464 Longitude: -109.587806 NAD 27 BTM HOLE LOCATION **NWSE** 2162 FSL 1828 FEL Sec 30 T 10S R 21E Latitude: 39.917295 -109.590891 NAD 27 Longitude: Wasatch/Mesaverde





KERR-McGEE OIL & GAS ONSHORE LP

DRILLING PROGRAM

CASING PROGRAM

| | | | | | | | | DESIGN FACTORS | | | |
|------------|--------|-------|------------|-------|-------|-------|-------|----------------|----------|---------|--|
| | SIZE | INTE | INTERVAL V | | WT. | GR. | CPLG. | BURST | COLLAPSE | TENSION | |
| CONDUCTOR | 14" | 0-40' | | | | | | | | | |
| | | | | | | | | 3,390 | 1,880 | 348,000 | |
| SURFACE | 8-5/8" | 0 | to | 2,080 | 28.00 | IJ-55 | LTC | 2.60 | 1.93 | 5.92 | |
| | | | | | | | | 7,780 | 6,350 | 367,000 | |
| PRODUCTION | 4-1/2" | 0 | to | 9,660 | 11.60 | I-80 | BTC | 1.11 | 1.04 | 4.05 | |
| | | | | | | | | | | | |

Surface Casing:

(Burst Assumptions: TD = 12.5 ppg) 0.73 psi/ft = frac gradient @ surface shoe

Fracture at surface shoe with 0.1 psi/ft gas gradient above

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

Production casing:

(Burst Assumptions: Pressure test with 8.4ppg @ 7000 psi) 0.64 psi/ft = bottomhole gradient

(Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing*Buoy.Fact. of water)

CEMENT PROGRAM

| | FT. OF FILL | DESCRIPTION | SACKS | EXCESS | WEIGHT | YIELD |
|----------------------|-------------|---|-------------|---------------|----------|-------|
| SURFACE LEAD | 500' | Premium cmt + 2% CaCl | 180 | 60% | 15.80 | 1.15 |
| Option 1 | | + 0.25 pps flocele | | | | |
| TOP OUT CMT (6 jobs) | 1,200' | 20 gals sodium silicate + Premium cmt | 270 | 0% | 15.80 | 1.15 |
| | | + 2% CaCl + 0.25 pps flocele | | | | |
| SURFACE | | NOTE: If well will circulate water to sur | face, optio | n 2 will be ι | ıtilized | |
| Option 2 LEAD | 1,580' | 65/35 Poz + 6% Gel + 10 pps gilsonite | 150 | 35% | 11.00 | 3.82 |
| | | + 0.25 pps Flocele + 3% salt BWOW | | | | |
| TAIL | 500' | Premium cmt + 2% CaCl | 150 | 35% | 15.80 | 1.15 |
| | | + 0.25 pps flocele | | | | |
| TOP OUT CMT | as required | Premium cmt + 2% CaCl | as req. | | 15.80 | 1.15 |
| PRODUCTION LEAD | 3,730' | Premium Lite II +0.25 pps | 270 | 10% | 11.00 | 3.38 |
| | | celloflake + 5 pps gilsonite + 10% gel | | | | |
| | | + 0.5% extender | | | | |
| TAIL | 5,930' | 50/50 Poz/G + 10% salt + 2% gel | 1,140 | 10% | 14.30 | 1.31 |
| | | + 0.1% R-3 | | | | |

^{*}Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

FLOAT EQUIPMENT & CENTRALIZERS

SURFACE

Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe

PRODUCTION

Float shoe, 1 jt, float collar. No centralizers will be used.

ADDITIONAL INFORMATION

 $\begin{tabular}{ll} \textbf{Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out. } \end{tabular}$

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

| Surveys will be taken at 1,000' minimum interv | als. |
|--|------|
|--|------|


Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

Kenny Gathings / Lovel Young


| DRILLING ENGINEER: | | DATE: | |
|--------------------------|-----------------------------|-------|--|
| | Nick Spence / Emile Goodwin | | |
| DRILLING SUPERINTENDENT: | | DATE: | |

^{*}Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained


EXHIBIT A
NBU 1021-30J1CS



SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK



| | | SURFACE POS | SITION | | | BOTTOM HOLE | | | | | |
|--|--|---|--|-----------------------------|-------------------------|--|--------------------------------|--|---|---|-----------------------------|
| WELL NAME | NAD83 | | NAD27 | | | | ND83 | | NAI | | |
| NBU | LATITUDE LONGITU 39°54'52.284" 109°35'18. | | | 5'16.075" | FOOTAGES 1179' FSL | 39°54'45.702 | | GITUDE 5'29.487" | LATITUDE 39°54'45.827" | LONGITUDE 109°35'27.008" | FOOTAGES 499' FSL |
| 1021-30O4BS | 39.914523° 109.58848 | | | 3 16.0/3 87799° | 971' FEL | 39.912695° | 109.59 | | 39.912730° | 109.590836° | 1831' FEL |
| NBU | 39°54'52.383" 109°35'18. | | | 5'16.084" | 1189' FSL | 39°54'48.833 | 1.00.00 | 5'12.441" | 39°54'48.958" | | 837' FSL |
| 1021-30P1CS NBU | 39.914551° 109.58849 39°54'52.481" 109°35'18. | | | 87801° 5'16.090" | 972 FEL 1199 FSL | 39.913565° 39°55'11.521 | 109.58 109°35 | 5'12.757" | 39.913599° 39°55'11.646" | 109.586101° 109°35'10.279" | 499' FEL 2175' FNL |
| 1021-30H4BS | 39.914578° 109.58849 | 1° 39.91461 | 3° 109.5 | 87803° | 972' FEL | 39.919867° | 109.58 | 36877° | 39.919902° | 109.586189° | 498' FEL |
| NBU 1021-30 1CS | 39°54'52.580" 109°35'18. 39.914606° 109.58849 | | | 5'16.100" 87806° | 1209' FSL 973' FEL | 39°55'02.137 39.917260° | 109°35 109.59 | 5'29.688" 91580° | 39°55'02.262" 39.917295° | 109°35'27.209" 109.590891° | 2162' FSL 1828' FEL |
| NBU 390 | 39°54'52.814" 109°35'18. | .491" 39°54'52. | 939" 109°3 | 5'16.013" | 1232' FSL | | 1103.33 | 71300 | | 103.330031 | TOZO TEE |
| | 39.914671° 109.58847 | | | 87781° | 966' FEL | Position to Bo | | | | | |
| WELL NAME | NORTH EAST | WELL NAME | NORTH | EAS | | | RTH | e EAST | WELL NAM | ME NORTH | EAST |
| NBU | -665.0' -853.1' | NBU | -360.0 | 476. | 6' NBU | 1 9 | 26.5 | 455.51 | NBU | 968 51 | -864.5 |
| 1021-30O4BS | 003.0 | 1021-30P1CS | 300.0 | | 1021-3 | BOH4BS 179 | | | 1021-30J1C | CS SOCIO | 001.3 |
| N N | Nais Roll of R | 3/1/2/3/3/3/3/3/3/3/3/3/3/3/3/3/3/3/3/3/ | | N03°40'11"W | Az=530.330z0 | $N13^{\circ}18^{\circ}15^{\circ}E_{-}$ T_{0} | | THE S.L.E GLO | SE ¼ OF SECT 3.&M. WHICH DBAL POSITIO | IGS IS THE EAS TON 30, T10S, HIS TAKEN FRO DNING SATELLI TO BEAR S00°3 | R21E, DM TE |
| cut-off b | for the Existing Well has below grade. Position de etal detector. | termined | 100 170° 100 100 100 100 100 100 100 100 100 1 | | - NBU | J 1021-30 J 1021-30 J 1021-30 | J1CS / H4BS P1CS O4BS | Az. to Exi Az. to Ex Az. to Ex Az. to Ex | st. W.H.=16.1 xist. W.H.=10 xist. W.H.=07 xist. W.H.=05 | .22556° 34.21 | |
| Casing tout-off by with me win the with me win | Gee Oil & Gas C Bth Street - Denver, Color L PAD - NBU 10 PAD INTERFEREN U 1021-3004BS, NBU 21-30H4BS & NBU 10 | Onshore, I Prado 80202 121-30P | -P | CONS 2155 No. | NBU NBU NBU NBU NBU NBU | U 1021-30 U 1021-30 U 1021-30 U 1021-30 | H4BS P1CS O4BS | Az. to Exi Az. to Ex Az. to Ex Az. to Ex Az. to Ex Az. to Ex Az. to Ex Az. to Ex BERLIN NEERIN NORTH 3 | INE G & LAND 100 WEST - VEF SURVEYED E | .22556° 34.2' .39500° 43.9' 5.26083° 53.8' SURVEYINC RNAL, UTAH 840 BY: D.J.S. | i, INC. 078 |
| Casing tout-off by with me win the with me win | Gee Oil & Gas C Bth Street - Denver, Color L PAD - NBU 10 PAD INTERFEREN U 1021-3004BS, NBU | Onshore, I Prado 80202 121-30P 1021-30P10 1021-3091CS 105, R21E, | -P | CONSI 2155 No Sherida | NBU NBU | J 1021-30 J 1021-30 J 1021-30 J 1021-30 | SCA | Az. to Exi Az. to Ex Az. to Ex Az. to Ex Az. to Ex Az. to Ex Az. to Ex Az. to Ex BERLIN NEERIN NORTH 3 | ist. W.H.=16.1 xist. W.H.=10 xist. W.H.=07 xist. W.H.=05 | (4: SURVEYINC RNAL, UTAH 840 BY: D.J.S. | |






PHOTO VIEW: FROM PIT CORNER D TO LOCATION STAKE





PHOTO VIEW: FROM END OF EXISTING ACCESS ROAD

CAMERA ANGLE: NORTHERLY

Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street - Denver, Colorado 80202

WELL PAD - NBU 1021-30P

LOCATION PHOTOS NBU 1021-30O4BS, NBU 1021-30P1CS, NBU 1021-30H4BS & NBU 1021-30J1CS LOCATED IN SECTION 30, T10S, R21E, S.L.B.&M., UINTAH COUNTY, UTAH.



CONSULTING, LLC Sheridan WY 82801

2155 North Main Street Phone 307-674-0609 Fax 307-674-0182


| | TIMBERLIN | 1E (4 | 35) 789-13 |
|---|--------------------|------------------------|-------------|
| | engineering | & LAND SURVEYING | G, INC. |
| | 209 NORTH 300 | WEST - VERNAL, UTAH 84 | 07 8 |
| I | DATE PHOTOS TAKEN: | | CLIFET |


H 84078 SHEET NO: PHOTOS TAKEN BY: D.J.S. 10-28-10


DATE DRAWN: DRAWN BY: B.M. 11-09-10 Date Last Revised:


9 OF 16


(435) 789-1365














Kerr-McGee Oil & Gas Onshore, LP WELL PAD – NBU 1021-30P WELLS – NBU 1021-30O4BS, NBU 1021-30P1CS, NBU 1021-30H4BS & NBU 1021-30J1CS Section 30, T10S, R21E, S.L.B.&M.

From the intersection of U.S. Highway 40 and Vernal Avenue in Vernal, Utah, proceed in a westerly direction along U.S. Highway 40 approximately 13.9 miles to the junction of State Highway 88. Exit left and proceed in a southerly direction along State Highway 88 approximately 16.8 miles to Ouray, Utah. From Ouray, proceed in a southerly direction along the Seep Ridge Road (County B Road 2810) approximately 15.4 miles to the intersection of a Class D County Road to the east. Exit left and proceed in an easterly direction along the Class D County Road approximately 1.2 miles to the intersection of the Cottonwood Wash Road (Class D County Road) to the north. Exit left and proceed in a northerly direction along the Cottonwood Wash Road approximately 0.5 miles to a service road to the northwest. Exit left and proceed in a northwesterly direction along the service road approximately 0.7 miles to the proposed location.

Total distance from Vernal, Utah to the proposed well location is approximately 48.5 miles in a southerly direction.

SHEET 16 OF 16

US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N UINTAH_NBU 1021-30P PAD NBU 1021-30J1CS

NBU 1021-30J1CS

Plan: NBU 1021-30J1CS (wp02)

Standard Planning Report

01 February, 2011



ARJ: Wollanum (0.66); ABD, 47,5 125370000

Site: UINTAH_NBU 1021-30P PAD Well: NBU 1021-30J1CS Wellbore: NBU 1021-30J1CS

Section: SHL:

+N/-S

+E/-W

Design: NBU 1021-30J1CS (wp02)

Latitude: 39.914640 Longitude: -109.587806

> Northing 0.00 14498093.80

GL: 5250.00 KB: (4' RKB + 5250' GL) @ 5254.00ft

FORMATION TOP DETAILS **TVDPath MDPath** Formation GREEN RIVER BIRDSNEST 1048.00 1279.00 1056.77 1299.13 1632.00 1682.50 MAHOGANY 4237.00 7181.00 4473.82 7418.19 WASATCH DARK CANYON 8163.00 8708.00 8400.19 MESAVERDE UPPER 8945.19 MESAVERDE LOWER





Magnetic North: 11.15°


Magnetic Field Strength: 52306.7snT Dip Angle: 65.79° Date: 1/25/2011 Model: IGRF2010


| WELL DETAILS: N | BU 1021-30J1CS | | |
|--|-----------------------------------|--------------------------|------|
| Ground Level: Easting 2036412.49 | 5250.00 Latittude 39.914640 | Longitude -109.587806 | Slot |

| Slot | TVD 2082.00 | MD 2174.90 | Name 8 5/8" | Size 8-5/8 | |
|------|----------------|---------------|----------------|---------------|--|
| | | | | | |

CASING DETAILS

| DESIGN TARGET DETAILS | | | | | | | | |
|-----------------------|---------|--------|---------|-------------|------------|-----------|-------------|------------------------|
| Name | TVD | +N/-S | +E/-W | Northing | Easting | Latitude | Longitude | Shape |
| NBU 1021-30J1CS BHL | 9423.00 | 966.95 | -865.18 | 14499046.95 | 2035532.13 | 39.917295 | -109.590891 | Circle (Radius: 25.00) |







Database: edm5000p

Company: US ROCKIES REGION PLANNING
Project: UTAH - UTM (feet), NAD27, Zone 12N

Site: UINTAH_NBU 1021-30P PAD

 Well:
 NBU 1021-30J1CS

 Wellbore:
 NBU 1021-30J1CS

 Design:
 NBU 1021-30J1CS (wp02)

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 1021-30J1CS

(4' RKB + 5250' GL) @ 5254.00ft (4' RKB + 5250' GL) @ 5254.00ft

True

Minimum Curvature

Project UTAH - UTM (feet), NAD27, Zone 12N

Map System: Universal Transverse Mercator (US Survey Fee System Datum:

Mean Sea Level

Geo Datum: NAD 1927 (NADCON CONUS)
Map Zone: Zone 12N (114 W to 108 W)

Site UINTAH_NBU 1021-30P PAD

Northing: 14,498,083.99 ft Site Position: Latitude: 39.914613 From: Lat/Long Easting: 2,036,413.49 ft Longitude: -109.587803 **Position Uncertainty:** 0.00 ft **Slot Radius: Grid Convergence:** 0.91°

Well NBU 1021-30J1CS

 Well Position
 +N/-S
 9.83 ft
 Northing:
 14,498,093.81 ft
 Latitude:
 39.914640

 +E/-W
 -0.84 ft
 Easting:
 2,036,412.49 ft
 Longitude:
 -109.587806

Position Uncertainty 0.00 ft Wellhead Elevation: Ground Level: 5,250.00 ft

Wellbore NBU 1021-30J1CS

 Magnetics
 Model Name
 Sample Date (°)
 Declination (°)
 Dip Angle (°)
 Field Strength (nT)

 IGRF2010
 1/25/2011
 11.15
 65.79
 52,307

Design NBU 1021-30J1CS (wp02)

Audit Notes:

Version: Phase: PLAN Tie On Depth: 0.00

 Vertical Section:
 Depth From (TVD) (ft) (ft)
 +N/-S (ft) (ft)
 +E/-W (ft) (ft)
 Direction (°)

 0.00
 0.00
 0.00
 318.18

| Plan Section | s | | | | | | | | | |
|---------------------------|--------------------|----------------|---------------------------|---------------|---------------|-----------------------------|----------------------------|---------------------------|------------|-----------------|
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) | TFO (°) | Target |
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 300.00 | 0.00 | 0.00 | 300.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 1,497.59 | 23.95 | 318.18 | 1,463.02 | 183.85 | -164.50 | 2.00 | 2.00 | 0.00 | 318.18 | |
| 3,391.51 | 23.95 | 318.18 | 3,193.84 | 756.84 | -677.18 | 0.00 | 0.00 | 0.00 | 0.00 | |
| 4,760.19 | 0.00 | 0.00 | 4,523.00 | 966.95 | -865.18 | 1.75 | -1.75 | 0.00 | 180.00 | |
| 9,660.19 | 0.00 | 0.00 | 9,423.00 | 966.95 | -865.18 | 0.00 | 0.00 | 0.00 | 0.00 | NBU 1021-30J1CS |



Database: Company: Project:

edm5000p

US ROCKIES REGION PLANNING UTAH - UTM (feet), NAD27, Zone 12N

UINTAH_NBU 1021-30P PAD Site:

NBU 1021-30J1CS Well: Wellbore: NBU 1021-30J1CS **Local Co-ordinate Reference:**

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 1021-30J1CS

(4' RKB + 5250' GL) @ 5254.00ft (4' RKB + 5250' GL) @ 5254.00ft

Minimum Curvature

| Design: | NBU 1021-3 | 0J1CS (wp02) | | | | | | | |
|--|-------------------------|----------------------------|----------------------------------|----------------------------|-------------------------------|-----------------------------|-----------------------------|----------------------------|---------------------------|
| Planned Survey | | | | | | | | | |
| Measured Depth (ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 100.00 | 0.00 | 0.00 | 100.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 200.00 | 0.00 | 0.00 | 200.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 300.00 | 0.00 | 0.00 | 300.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 | 0.00 |
| 400.00 | 2.00 | 318.18 | 399.98 | 1.30 | -1.16 | 1.75 | 2.00 | 2.00 | 0.00 |
| 500.00 | 4.00 | 318.18 | 499.84 | 5.20 | -4.65 | 6.98 | 2.00 | 2.00 | 0.00 |
| 600.00 | 6.00 | 318.18 | 599.45 | 11.70 | -10.46 | 15.69 | 2.00 | 2.00 | 0.00 |
| 700.00 | 8.00 | 318.18 | 698.70 | 20.78 | -18.59 | 27.88 | 2.00 | 2.00 | 0.00 |
| 800.00 | 10.00 | 318.18 | 797.47 | 32.43 | -29.02 | 43.52 | 2.00 | 2.00 | 0.00 |
| 900.00 | 12.00 | 318.18 | 895.62 | 46.65 | -41.74 | 62.60 | 2.00 | 2.00 | 0.00 |
| 1,000.00 | 14.00 | 318.18 | 993.06 | 63.42 | -56.74 | 85.10 | 2.00 | 2.00 | 0.00 |
| 1,056.77 | 15.14 | 318.18 | 1,048.00 | 74.06 | -66.26 | 99.38 | 2.00 | 2.00 | 0.00 |
| 1,100.00 | 16.00 | 318.18 | 1,089.64 | 82.70 | -74.00 | 110.98 | 2.00 | 2.00 | 0.00 |
| 1,200.00 | 18.00 | 318.18 | 1,185.27 | 104.49 | -93.49 | 140.21 | 2.00 | 2.00 | 0.00 |
| 1,299.13 | 19.98 | 318.18 | 1,279.00 | 128.53 | -115.00 | 172.47 | 2.00 | 2.00 | 0.00 |
| 1,300.00 | 20.00 | 318.18 | 1,279.82 | 128.75 | -115.20 | 172.77 | 2.00 | 2.00 | 0.00 |
| 1,400.00 | 22.00 | 318.18 | 1,373.17 | 155.46 | -139.10 | 208.60 | 2.00 | 2.00 | 0.00 |
| 1,497.59 | 23.95 | 318.18 | 1,463.02 | 183.85 | -164.50 | 246.70 | 2.00 | 2.00 | 0.00 |
| 1,500.00 | 23.95 | 318.18 | 1,465.22 | 184.58 | -165.15 | 247.67 | 0.00 | 0.00 | 0.00 |
| 1,600.00 | 23.95 | 318.18 | 1,556.60 | 214.83 | -192.22 | 288.27 | 0.00 | 0.00 | 0.00 |
| 1,682.50 MAHOGAN | 23.95 Y | 318.18 | 1,632.00 | 239.79 | -214.55 | 321.76 | 0.00 | 0.00 | 0.00 |
| 1,700.00 | 23.95 | 318.18 | 1,647.99 | 245.08 | -219.29 | 328.87 | 0.00 | 0.00 | 0.00 |
| 1,800.00 | 23.95 | 318.18 | 1,739.38 | 275.34 | -246.36 | 369.46 | 0.00 | 0.00 | 0.00 |
| 1,900.00 | 23.95 | 318.18 | 1,830.77 | 305.59 | -273.43 | 410.06 | 0.00 | 0.00 | 0.00 |
| 2,000.00 | 23.95 | 318.18 | 1,922.16 | 335.85 | -300.50 | 450.66 | 0.00 | 0.00 | 0.00 |
| 2,100.00 | 23.95 | 318.18 | 2,013.55 | 366.10 | -327.57 | 491.25 | 0.00 | 0.00 | 0.00 |
| 2,174.90 | 23.95 | 318.18 | 2,082.00 | 388.76 | -347.84 | 521.66 | 0.00 | 0.00 | 0.00 |
| 8 5/8" 2,200.00 2,300.00 2,400.00 | 23.95 23.95 23.95 | 318.18 318.18 318.18 | 2,104.94 2,196.32 2,287.71 | 396.36 426.61 456.86 | -354.64 -381.71 -408.78 | 531.85 572.45 613.05 | 0.00 0.00 0.00 | 0.00 0.00 0.00 | 0.00 0.00 0.00 |
| 2,500.00 | 23.95 | 318.18 | 2,379.10 | 487.12 | -435.85 | 653.64 | 0.00 | 0.00 | 0.00 |
| 2,600.00 | 23.95 | 318.18 | 2,470.49 | 517.37 | -462.92 | 694.24 | 0.00 | 0.00 | 0.00 |
| 2,700.00 | 23.95 | 318.18 | 2,561.88 | 547.63 | -489.99 | 734.84 | 0.00 | 0.00 | 0.00 |
| 2,800.00 | 23.95 | 318.18 | 2,653.27 | 577.88 | -517.06 | 775.43 | 0.00 | 0.00 | 0.00 |
| 2,900.00 | 23.95 | 318.18 | 2,744.66 | 608.14 | -544.13 | 816.03 | 0.00 | 0.00 | 0.00 |
| 3,000.00 | 23.95 | 318.18 | 2,836.05 | 638.39 | -571.20 | 856.63 | 0.00 | 0.00 | 0.00 |
| 3,100.00 | 23.95 | 318.18 | 2,927.43 | 668.64 | -598.27 | 897.22 | 0.00 | 0.00 | 0.00 |
| 3,200.00 | 23.95 | 318.18 | 3,018.82 | 698.90 | -625.34 | 937.82 | 0.00 | 0.00 | 0.00 |
| 3,300.00 | 23.95 | 318.18 | 3,110.21 | 729.15 | -652.41 | 978.42 | 0.00 | 0.00 | 0.00 |
| 3,391.51 | 23.95 | 318.18 | 3,193.84 | 756.84 | -677.18 | 1,015.57 | 0.00 | 0.00 | 0.00 |
| 3,400.00 | 23.80 | 318.18 | 3,201.60 | 759.40 | -679.47 | 1,019.00 | 1.75 | -1.75 | 0.00 |
| 3,500.00 | 22.05 | 318.18 | 3,293.70 | 788.43 | -705.45 | 1,057.96 | 1.75 | -1.75 | 0.00 |
| 3,600.00 | 20.30 | 318.18 | 3,386.94 | 815.35 | -729.54 | 1,094.09 | 1.75 | -1.75 | 0.00 |
| 3,700.00 | 18.55 | 318.18 | 3,481.24 | 840.14 | -751.71 | 1,127.35 | 1.75 | -1.75 | 0.00 |
| 3,800.00 | 16.80 | 318.18 | 3,576.52 | 862.77 | -771.96 | 1,157.71 | 1.75 | -1.75 | 0.00 |
| 3,900.00 | 15.05 | 318.18 | 3,672.68 | 883.22 | -790.26 | 1,185.16 | 1.75 | -1.75 | 0.00 |
| 4,000.00 | 13.30 | 318.18 | 3,769.63 | 901.48 | -806.59 | 1,209.65 | 1.75 | -1.75 | 0.00 |
| 4,100.00 | 11.55 | 318.18 | 3,867.28 | 917.51 | -820.94 | 1,231.17 | 1.75 | -1.75 | 0.00 |
| 4,200.00 | 9.80 | 318.18 | 3,965.54 | 931.32 | -833.30 | 1,249.70 | 1.75 | -1.75 | 0.00 |
| 4,300.00 | 8.05 | 318.18 | 4,064.33 | 942.89 | -843.65 | 1,265.22 | 1.75 | -1.75 | 0.00 |



Database: Company: Project:

edm5000p

US ROCKIES REGION PLANNING

UTAH - UTM (feet), NAD27, Zone 12N UINTAH_NBU 1021-30P PAD

Site: Well: NBU 1021-30J1CS NBU 1021-30J1CS Wellbore: Design:

NBU 1021-30J1CS (wp02)

Local Co-ordinate Reference:

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 1021-30J1CS

(4' RKB + 5250' GL) @ 5254.00ft (4' RKB + 5250' GL) @ 5254.00ft

Minimum Curvature

| Design: | | NBU 1021-3 | 0J1CS (wp02) | | | | | | | |
|--------------------------------------|------------------------------|--|--|--|--|---|--|--|--|--|
| Planned Surv | ey | | | | | | | | | |
| Measu Dept (ft) | red :h | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 4,40 4,47 WAS | | 6.30 5.01 | 318.18 318.18 | 4,163.54 4,237.00 | 952.20 957.62 | -851.98 -856.83 | 1,277.71 1,284.99 | 1.75 1.75 | -1.75 -1.75 | 0.00 0.00 |
| 4,50 4,60 4,70 | 0.00 0.00 | 4.55 2.80 1.05 | 318.18 318.18 318.18 | 4,263.09 4,362.88 4,462.82 | 959.25 964.03 966.54 | -858.29 -862.56 -864.81 | 1,287.17 1,293.59 1,296.95 | 1.75 1.75 1.75 | -1.75 -1.75 -1.75 | 0.00 0.00 0.00 |
| 4,76 4,80 4,90 5,00 5,10 | 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 4,523.00 4,562.81 4,662.81 4,762.81 4,862.81 | 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 1.75 0.00 0.00 0.00 0.00 | -1.75 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 |
| 5,20 5,30 5,40 5,50 5,60 | 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 4,962.81 5,062.81 5,162.81 5,262.81 5,362.81 | 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 |
| 5,70 5,80 5,90 6,00 6,10 | 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 5,462.81 5,562.81 5,662.81 5,762.81 5,862.81 | 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 |
| 6,20 6,30 6,40 6,50 6,60 | 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 5,962.81 6,062.81 6,162.81 6,262.81 6,362.81 | 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 |
| 6,70 6,80 6,90 7,00 7,10 | 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 6,462.81 6,562.81 6,662.81 6,762.81 6,862.81 | 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 |
| 7,20 7,30 7,40 7,41 | 0.00 | 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 | 6,962.81 7,062.81 7,162.81 7,181.00 | 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 |
| 7,70 7,80 | 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 0.00 | 7,262.81 7,362.81 7,462.81 7,562.81 7,662.81 7,762.81 | 966.95 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 0.00 |
| 8,10 8,20 8,30 8,40 8,40 | 0.00 0.00 0.00 0.19 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 7,862.81 7,962.81 8,062.81 8,162.81 8,163.00 | 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 |
| 8,50 8,60 8,70 8,80 8,90 | 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 8,262.81 8,362.81 8,462.81 8,562.81 8,662.81 | 966.95 966.95 966.95 966.95 966.95 | -865.18 -865.18 -865.18 -865.18 -865.18 | 1,297.51 1,297.51 1,297.51 1,297.51 1,297.51 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 | 0.00 0.00 0.00 0.00 0.00 |



Database: Company: Project:

edm5000p

US ROCKIES REGION PLANNING UTAH - UTM (feet), NAD27, Zone 12N

UINTAH_NBU 1021-30P PAD

Site: Well: NBU 1021-30J1CS NBU 1021-30J1CS Wellbore: Design: NBU 1021-30J1CS (wp02) **Local Co-ordinate Reference:**

TVD Reference: MD Reference: North Reference:

Survey Calculation Method:

Well NBU 1021-30J1CS

(4' RKB + 5250' GL) @ 5254.00ft (4' RKB + 5250' GL) @ 5254.00ft

Minimum Curvature

| Planned Su | rvey | | | | | | | | | |
|------------|---------------------|--------------------|----------------|---------------------------|---------------|---------------|-----------------------------|-----------------------------|----------------------------|---------------------------|
| De | sured pth ft) | Inclination (°) | Azimuth (°) | Vertical Depth (ft) | +N/-S (ft) | +E/-W (ft) | Vertical Section (ft) | Dogleg Rate (°/100ft) | Build Rate (°/100ft) | Turn Rate (°/100ft) |
| 8,9 | 945.19 | 0.00 | 0.00 | 8,708.00 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| ME | SAVER | DE LOWER | | | | | | | | |
| 9,0 | 00.00 | 0.00 | 0.00 | 8,762.81 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| 9,1 | 100.00 | 0.00 | 0.00 | 8,862.81 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| 9,2 | 200.00 | 0.00 | 0.00 | 8,962.81 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| 9,3 | 300.00 | 0.00 | 0.00 | 9,062.81 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| 9,4 | 400.00 | 0.00 | 0.00 | 9,162.81 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| 9,5 | 500.00 | 0.00 | 0.00 | 9,262.81 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| 9,6 | 00.00 | 0.00 | 0.00 | 9,362.81 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| 9,6 | 660.19 | 0.00 | 0.00 | 9,423.00 | 966.95 | -865.18 | 1,297.51 | 0.00 | 0.00 | 0.00 |
| NB | U 1021- | 30J1CS BHL | | | | | | | | |

| Design Targets | | | | | | | | | |
|---------------------------------------|------------------|-----------------|-------------|---------------|---------------|------------------|-----------------|-----------|-------------|
| Target Name - hit/miss target - Shape | Dip Angle (°) | Dip Dir. (°) | TVD (ft) | +N/-S (ft) | +E/-W (ft) | Northing (ft) | Easting (ft) | Latitude | Longitude |
| NBU 1021-30J1CS E | | 0.00 | 9,423.00 | 966.95 | -865.18 | 14,499,046.95 | 2,035,532.13 | 39.917295 | -109.590891 |

plan hits target centerCircle (radius 25.00)

| Casing Points | | | | | |
|----------------------|---------------------------|---------------------------|--------|---------------------------|-------------------------|
| | Measured Depth (ft) | Vertical Depth (ft) | Name | Casing Diameter (") | Hole Diameter (") |
| | 2,174.90 | 2,082.00 | 8 5/8" | 8-5/8 | 11 |

| Formations | | | | | | | |
|------------|---------------------------|---------------------------|-----------------|-----------|------------|-------------------------|--|
| | Measured Depth (ft) | Vertical Depth (ft) | Name | Lithology | Dip (°) | Dip Direction (°) | |
| | 1,056.77 | 1,048.00 | GREEN RIVER | | | | |
| | 1,299.13 | 1,279.00 | BIRDSNEST | | | | |
| | 1,682.50 | 1,632.00 | MAHOGANY | | | | |
| | 4,473.82 | 4,237.00 | WASATCH | | | | |
| | 7,418.19 | 7,181.00 | DARK CANYON | | | | |
| | 8,400.19 | 8,163.00 | MESAVERDE UPPER | | | | |
| | 8,945.19 | 8,708.00 | MESAVERDE LOWER | | | | |

NBU 1021-30H4BS

Surface: 1,199' FSL 972' FEL (SE/4SE/4) BHL: 2,175' FNL 498' FEL (SE/4NE/4)

NBU 1021-30J1CS

Surface: 1,209' FSL 973' FEL (SE/4SE/4) BHL: 2,162' FSL 1,828' FEL (NW/4SE/4)

NBU 1021-3004BS

Surface: 1,179' FSL 971' FEL (SE/4SE/4) BHL: 499' FSL 1,831' FEL (SW/4SE/4)

NBU 1021-30P1CS

Surface: 1,189' FSL 972' FEL (SE/4SE/4) BHL: 837' FSL 499' FEL (SE/4SE/4)

> Pad: NBU 1021-30P Section 30 T10S R21E Mineral Lease: ML 22793

Uintah County, Utah Operator: Kerr-McGee Oil & Gas Onshore LP

MULTI-POINT SURFACE USE PLAN of OPERATIONS (SUPO)

This SUPO contains surface operating procedures for Kerr-McGee Oil & Gas Onshore LP (KMG), a wholly owned subsidiary of Anadarko Petroleum Corporation (APC) pertaining to actions that involve the State of Utah School and Institutional Trust Lands Administration (SITLA) in the development of minerals leased to APC/KMG (including, but not limited to, APDs/SULAs/ROEs/ROWs and/or easements).

See associated Utah Division of Oil, Gas, and Mining (UDOGM) Form 3(s), plats, maps, and other attachments for site-specific information on projects represented herein.

In accordance with Utah Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling, these wells will be directionally drilled. Refer to Topo Map A for directions to the location and Topo Maps A and B for location of access roads within a 2-mile radius.

A. **Existing Roads:**

Existing roads consist of county roads and improved/unimproved lease roads. APC/KMG will maintain existing roads in a condition that is the same as or better than before operations began and in a safe and usable condition. Maintenance of existing roads will continue until final abandonment and reclamation of well pads and/or other facilities. The road maintenance may include, but is not limited to, blading, ditching, culvert installation/cleanout, surfacing, and dust control.

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

Typically, roads, gathering lines and electrical distribution lines will occupy common disturbance corridors and roadways will be used as working space. All disturbances located in the same corridor will overlap each other to the maximum extent possible; in no case will the maximum disturbance width of the access road and utility corridors exceed 50', unless otherwise approved.

B. Planned Access Roads:

Approximately ± 475 ' (0.1 miles) of new road is proposed (see Topo Map B). Applicable Uintah County encroachment and/or pipeline crossing permits will be obtained prior to construction/development. No other pipelines will be crossed at this location.

Where roads are new or to be reconstructed, they will be located, designed, and maintained to meet the standards of SITLA and other commonly accepted Best Management Practices (BMPs). If a new road/corridor were to cross a water of the United States, KMG will adhere to the requirements of applicable Nationwide or Individual Permits of the Department of Army Corps of Engineers.

Turnouts; major cut and fills; culverts; bridges; gates; cattle guards; low water crossings; or modifications needed to existing infrastructure/facilities were determined at the on-site and, as applicable, are typically shown on attached Exhibits and Topo maps.

C. Location of Existing and Proposed Facilities:

Production facilities (see Well Pad Design Summary and Facilities Diagram):

This pad will expand the existing pad for the NBU 390. This well location is a Plugged and Abandoned well according to Utah Division of Oil, Gas and Mining (UDOGM) records as of January 20, 2011.

Production facilities will be installed on the disturbed portion of each well pad and may include bermed components (typically excluding dehy's and/or separators) that contain fluids (i.e. production tanks, produced liquids tanks). The berms will be constructed of compacted subsoil or corrugated metal, impervious, designed to hold 110% of the capacity of the largest tank, and be independent of the back cut. All permanent (on-site six months or longer) aboveground structures constructed or installed, including pumping units, will be painted a flat, non-reflective, earth-tone color chosen at the onsite in coordination with SITLA.

Production tanks will be constructed, maintained, and operated to prevent unauthorized surface or subsurface discharges of liquids and to prevent livestock or wildlife entry. The tanks are not to be used for disposal of liquids from additional sources without prior approval of UDOGM. Gathering facilities:

The following pipeline transmission facilities will apply if the well is productive (see Topo D):

The total gas gathering (steel line pipe with fusion bond epoxy coating) pipeline distances from the meter to the tie in point is $\pm 4,120$ ' and the individual segments are broken up as follows:

±480' (0.1 miles) –New 6" buried gas pipeline from the meter to the edge of the pad.

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

- ±25' (0.01 miles) –New 6" buried gas pipeline from the edge of pad to the NBU 1021-30F Pad intersection.
- ±3,615' (0.7 miles) –New 12" buried gas pipeline from the proposed NBU 1021-30F to the previously proposed 16" gas pipeline.

The total liquid gathering pipeline distance from the separator to the tie in point is $\pm 4,120$ and the individual segments are broken up as follows:

- ± 480 ' (0.1 miles) –New 6" buried liquid pipeline from the separator to the edge of the pad. ± 25 ' (0.01 miles) –New 6" buried liquid pipeline from the edge of pad to the NBU 1021-30F Pad intersection.
- ±3,615' (0.7 miles) –New 6" buried liquid pipeline from NBU 1021-30F Pad intersection to the previously proposed liquid pipeline.

The liquid gathering lines will be made of polyethylene or a composite polyethylene/steel or polyethylene/fiberglass that is not subject to internal or external pipe corrosion. The content of the produced fluids to be transferred by the liquid gathering system will be approximately 92% produced water and 8% condensate. Trunk line valve connections for the water gathering system will be below ground but accessible from the surface in order to prevent freezing during winter time.

The proposed pipelines will be buried and will include gas gathering and liquid gathering pipelines in the same trench. Where the pipeline is adjacent to the road or well pad, the road and/or well pad will be utilized for construction activities and staging. Kerr-McGee requests a permanent 30' right-of-way adjacent to the road for life-of-project for maintenance, repairs, and/or upgrades, no additional right-of-way will be needed beyond the 30'. Where the pipeline is not adjacent to the road or well pad, Kerr-McGee requests a temporary 45' construction right-of-way and 30' permanent right-of-way.

The proposed trench width for the pipeline would range from 18-48 inches and will be excavated to a depth of 48 to 60 inches of normal soil cover or 24 inches of cover in consolidated rock. During construction blasting may occur along the proposed right-of-way where trenching equipment cannot cut into the bedrock. Large debris and rocks removed from the earth during trenching and blasting that could not be returned to the trench would be distributed evenly and naturally in the project area. The proposed pipelines will be pressure tested pneumatically (depending on size) or with fluids (either fresh or produced). If fluids are used, there will be no discharge to the surface.

Pipeline signs will be installed along the right-of-way to indicate the pipeline proximity, ownership, and to provide emergency contact phone numbers. Above ground valves, T's, and/or cathodic protection will be installed at various locations for connection, corrosion prevention and/or for safety purposes.

D. <u>Location and Type of Water Supply:</u>

Water for drilling purposes will be obtained from one of the following sources:

• Dalbo Inc.'s underground well located in Ouray, Utah, Sec. 32 T4S R3E, Water User Claim number 43-8496, application number 53617.

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

• Price Water Pumping Inc. Green River and White River, various sources, Water Right Number 49-1659, application number: a35745.

Water will be hauled to location over the roads marked on Maps A and B. No water well is to be drilled on this lease.

E. Source of Construction Materials:

Construction operations will typically be completed with native materials found on location. If needed, construction materials that must be imported to the site (mineral material aggregate, soils or materials suitable for fill/surfacing) will be obtained from a nearby permitted source and described in subsequent Sundry requests. No construction materials will be removed from State lands without prior approval from SITLA.

F. Methods of Handling Waste Materials:

Should the well be productive, produced water will be contained in a water tank and will be transported by pipeline and/or truck to an approved disposal sites facilities and/or Salt Water Disposal (SWD) injection well. Currently, those facilities are:

RNI in Sec. 5 T9S R22E

Ace Oilfield in Sec. 2 T6S R20E MC&MC in Sec. 12 T6S R19E

Pipeline Facility in Sec. 36 T9S R20E

Goat Pasture Evaporation Pond in SW/4 Sec. 16 T10S R22E

Bonanza Evaporation Pond in Sec. 2 T10S R23E

Ouray #1 SWD in Sec. 1 T9S R21E NBU 159 SWD in Sec. 35 T9S R21E CIGE 112D SWD in Sec. 19 T9S R21E CIGE 114 SWD in Sec. 34 T9S R21E NBU 921-34K SWD in Sec. 34 T9S R21E NBU 921-33F SWD in Sec. 33 T9S R21E NBU 921-34L SWD in Sec. 34 T9S R21E

Drill cuttings and/or fluids will be contained in the reserve/frac pit. Cuttings will be buried in pit(s) upon closure. Unless otherwise approved, no oil or other oil-based drilling additives, chromium/metals-based, or saline muds will be used during drilling. Only fresh water (as specified above), biodegradable polymer soap, bentonite clay, and/or non-toxic additives will be used in the mud system.

Pits will be constructed to minimize the accumulation of surface runoff. Should fluid hydrocarbons be encountered during drilling, completions or well testing, product will either be contained in test tanks on the well site or evacuated by vacuum trucks and transported to an approved disposal/sales facility. Should petroleum hydrocarbons unexpectedly be released into a pit, they will be removed as soon as practical but in no case will they remain longer than 72 hours unless an alternate is approved by SITLA. Should timely removal prove infeasible, the pit will be netted with mesh no larger than 1 inch until such time as

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

hydrocarbons can be removed. Hydrocarbon removal will also take place prior to the closure of the pit, unless authorization is provided for disposal via alternative pit closure methods (e.g. solidification).

The reserve and/or fracture stimulation pit will be lined with a synthetic material 20-mil or thicker, The liner will be installed over smooth fill subgrade that is free of pockets, loose rocks, or other materials (i.e. sand, sifted dirt, bentonite, straw, etc.) that could damage the liner. Any additional pits necessary to subsequent operations, such as temporary flare or workover pits, will be contained within the originally approved well pad and disturbance boundaries. Such temporary pits will be backfilled and reclaimed within 180 days of completion of work at a well location.

For the protection of livestock and wildlife, all open pits and cellars will be fenced/covered to prevent wildlife or livestock entry. Total height of pit fencing will be at least 42 inches and corner posts will be cemented and/or braced in such a manner as to keep the fence tight at all times. Standard steel, wood, or pipe posts shall be used between the corner braces. Maximum distance between any 2 fence posts shall be no greater than 16 feet.

Pits containing drilling cuttings, mud, and/or completions fluids will be allowed to dry. Any free fluids remaining after six (6) months from reaching total depth, date of completion, and/or determination of inactivity will be removed (as weather conditions allow) to an approved site and the pit reclaimed. Additional drying methods may include fly-ash solidification or sprinkler evaporation. Installation and operation of any sprinklers, pumps, and equipment will ensure that water spray or mist does not drift. Reserve pit liners will be cut off or folded as near to the mud surface as possible and as safety considerations allow and buried on location.

No garbage or non-exempt substances as defined by Resource Conservation and Recovery Act (RCRA) subtitle C will be placed in the reserve pit. All refuse generated during construction, drilling, completion, and well testing activities will be contained in an enclosed receptacle, removed from the drill locations promptly, and transported to an approved disposal facility.

Portable, self-contained chemical toilets and/or sewage processing facilities will be provided for human waste disposal. Upon completion of operations, or as required, the toilet holding tanks will be pumped and the contents disposed of in an approved sewage disposal facility. All applicable regulations pertaining to disposal of human and solid waste will be observed.

Any undesirable event, accidental release, or in excess of reportable quantities will be managed according to the notification requirements of UDOGMs "Reporting Oil and Gas Undesirable Events" rule, and, where State wells are participatory to a Federal agreement, according to NTL-3A.

Materials Management

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

Hazardous materials above reportable quantities will not be produced by drilling or completing proposed wells or constructing the pipelines/facilities. The term "hazardous materials" as used here means: (1) any substance, pollutant, or containment listed as hazardous under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA) of 1980, as amended 42 U.S.C. 9601 et seq., and the regulations issued under CERCLA; and (2) any hazardous waste as defined in RCRA of 1976, as amended. In addition, no extremely hazardous substance, as defined in 40 CFR 355, in threshold planning quantities, would be used, produced, stored, transported, or disposed of while producing any well.

Chemicals subject to reporting under Title III of the Superfund Amendments and Reauthorization Act (SARA) in quantities of 10,000 pounds or more may be produced and/or stored at production facilities and may be kept in limited quantities on drilling sites and well locations for short periods of time during drilling or completion activities.

G. Ancillary Facilities:

None are anticipated.

H. Well Site Layout (see Well Pad Design Summary):

The location, orientation and aerial extent of each drill pad; reserve/completion/flare pit; access road ingress/egress points, drilling rig, dikes/ditches, existing wells/infrastructure; proposed cuts and fills; and topsoil and spoil material stockpile locations are depicted on the exhibits for each project, where applicable. Site-specific conditions may require slight deviation in actual equipment and facility layout; however, the area of disturbance, as described in the survey, will not be exceeded.

Coordinates are provided in the National Spatial Reference System, North American Datum, 1983 (NAD83) or latest edition. Distances are depicted on each plat to the nearest two adjacent section lines.

I. Plans for Reclamation of the Surface:

Surface reclamation will be undertaken in two phases: interim and final. Interim reclamation is conducted following well completion and extends through the period of production. This reclamation is for the area of the well pad that is not required for production activities. Final reclamation is conducted following well plugging/conversion and/or facility abandonment processes.

Reclamation activities in both phases may include but are not limited to: re-contouring or re-configuration of topographic surfaces, restoration of drainage systems, segregation of spoils materials, minimizing surface disturbance, re-evaluating backfill requirements, pit closure, topsoil redistribution, soil treatments, seeding and weed control.

Interim Reclamation

Interim reclamation includes pit closure, re-contouring (where possible), soil bed preparation, topsoil

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

placement, seeding, and/or weed control.

Interim re-contouring involves bringing all construction material from cuts and fills back onto the well pad and site and reestablishing the natural contours where desirable and practical. Fill and stockpiled spoils no longer necessary to the operation will be spread on the cut slopes and covered with stockpiled topsoil. All stockpiled top soils will be used for interim reclamation where practical to maintain soil viability. Where possible, the land surface will be left "rough" after re-contouring to ensure that the maximum surface area will be available to support the reestablishment of vegetative cover.

A reserve pit, upon being allowed to dry, will be backfilled and compacted with cover materials that are void of any topsoil, vegetation, large stones, rocks or foreign objects. Soils that are moisture laden, saturated, or partially/completely frozen will not be used for backfill or cover. The pit area will be mounded to allow for settling and to promote positive surface drainage away from the pit.

Final Reclamation

Final reclamation will be performed for newly drilled unproductive wells and/or at the end of the life of a productive well. As soon as practical after the conclusion of drilling and testing operations, unproductive drill holes will be plugged and abandoned (P&A). Site and road reclamation will commence following plugging. In no case will reclamation at non-producing locations be initiated later than six (6) months from the date a well is plugged. A joint inspection of the disturbed area to be reclaimed may be requested by APC/KMG. The primary purpose of this inspection will be to review the existing conditions, or agree upon a revised final reclamation and abandonment plan. A Notice of Intent to Abandon will be filed for final recommendations regarding surface reclamation.

After plugging, all wellhead equipment that is no longer needed will be removed, and the well site will be reclaimed. Final contouring will blend with and follow as closely as practical the natural terrain and contours of the original site and surrounding areas. After re-contouring, final grading will be conducted over the entire surface of the well site and access road. Where practical, the area will be ripped to a depth of 18 to 24 inches on 18 to 24-inch centers and surface materials will be pitted with small depressions to form longitudinal depressions 12 to 18 inches deep perpendicular to the natural flow of water.

All unnecessary surface equipment and structures (e.g. cattle guards) and water control structures (e.g. culverts, drainage pipes) not needed to facilitate successful reclamation will be removed during final reclamation. Roads that will be reclaimed will be ripped to a depth of 18 inches where practical, re-contoured to approximate the original contour of the ground and seeded.

Upon successfully completing reclamation of a P&A location, a Final Abandonment Notice will be submitted to UDOGM.

Seeding and Measures Common to Interim and Final Reclamation

Reclaimed areas may be fenced to exclude grazing and encourage re-vegetation.

Surface Use Plan of Operations Page 8

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

On slopes where severe erosion can become a problem and the use of machinery is not practical, seed will be hand broadcast and raked with twice the specified amount of seed. The slope will be stabilized using materials specifically designed to prevent erosion on steep slopes and hold seed in place so vegetation can become permanently established. These materials will include, but are not limited to, erosion control blankets and bonded fiber matrix at a rate to achieve a minimum of 80 percent soil coverage.

Seeding will occur year-round as conditions allow. Seed mixes appropriate to the native plant community as determined and specified for each project location based on the site specific soils will be used for revegetation. The site specific seed mix will be provided by SITLA.

J. <u>Surface/Mineral Ownership</u>:

SITLA 675 East 500 South, Suite 500 Salt Lake City, UT 84102

K. Other Information:

None

NBU 1021-30H4BS / 30J1CS/ 30O4BS/ 30P1CS

M. <u>Lessee's or Operators' Representative & Certification:</u>

Danielle Piernot Regulatory Analyst I Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6156 Tommy Thompson General Manager, Drilling Kerr-McGee Oil & Gas Onshore LP PO Box 173779 Denver, CO 80217-3779 (720) 929-6724

Certification: All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws, regulations, Onshore Oil and Gas Orders, the approved Plan of Operations, and any applicable Notice to Lessees.

The Operator will be fully responsible for the actions of its subcontractors. A complete copy of the approved "Application for Permit to Drill" will be furnished to the field representative(s) to ensure compliance and shall be on location during all construction and drilling operations.

Kerr-McGee Oil & Gas Onshore LP is considered to be the operator of the subject well. Kerr-McGee Oil & Gas Onshore LP agrees to be responsible under terms and conditions of the lease for the operations conducted upon leased lands.

Bond coverage for State lease activities is provided by State Surety Bond 22013542, and for applicable Federal lease activities and pursuant to 43 CFR 3104, by Bureau of Land Management Nationwide Bond WYB000291.

I hereby certify that I, or persons under my supervision, have inspected the proposed drill site and access route, that I am familiar with the conditions that currently exist; that I have full knowledge of the State and Federal laws applicable to this operation; that the statements made in this plan are, to the best of my knowledge, true and correct; and the work associated with the operations proposed herein will be performed in conformity with this APD package and the terms and conditions under which it is approved. I also certify that I, or the company I represent, am responsible for operations conducted under this application. These statements are subject to the provisions of 18 U.S.C. 1001 for the filing of false statements.

Danielle Piernot

March 11, 2011

Date



Kerr-McGee Oil & Gas Onshore LP PO Box 173779 DENVER, CO 80217-3779

January 17, 2011

Ms. Diana Mason Division of Oil, Gas and Mining P.O. Box 145801 Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11

NBU 1021-30J1CS

T10S-R21E

Section 30: SESE (Surf), NWSE (Bottom)

Surface: 973' FEL, 1209' FSL Bottom Hole: 1828' FEL, 2162' FSL

Uintah County, Utah

Dear Ms. Mason:

Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to Directional Drilling.

- Kerr-McGee's NBU 1021-30J1CS is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore.


Therefore, based on the above stated information, Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

Ptt.

Robert Spencer Landman II



United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office
P.O. Box 45155
Salt Lake City, Utah 84145-0155

IN REPLY REFER TO: 3160 (UT-922)

March 16, 2011

Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2011 Plan of Development Natural Buttes Unit

Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2011 within the Natural Buttes Unit, Uintah County, Utah.

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

NBU 1021-30P PAD

43-047-51510 NBU 1021-3004BS Sec 30 T10S R21E 1179 FSL 0971 FEL BHL Sec 30 T10S R21E 0499 FSL 1831 FEL 43-047-51511 NBU 1021-30P1CS Sec 30 T10S R21E 1189 FSL 0972 FEL BHL Sec 30 T10S R21E 0837 FSL 0499 FEL **NBU 1021-32F PAD** 43-047-51512 NBU 1021-32C4BS Sec 32 T10S R21E 1872 FNL 2121 FWL BHL Sec 32 T10S R21E 0825 FNL 2188 FWL 43-047-51513 NBU 1021-32D4BS Sec 32 T10S R21E 1860 FNL 2105 FWL BHL Sec 32 T10S R21E 0825 FNL 0842 FWL Sec 32 T10S R21E 1866 FNL 2113 FWL 43-047-51514 NBU 1021-32E4BS BHL Sec 32 T10S R21E 2072 FNL 0841 FWL 43-047-51515 NBU 1021-32F4BS Sec 32 T10S R21E 1878 FNL 2129 FWL BHL Sec 32 T10S R21E 2053 FNL 2191 FWL **NBU 1021-28F PAD** BHL Sec 28 T10S R21E 0831 FNL 2151 FWL

| API # WE | ELL 1 | NAME | | L(| OCATI(| ON | | | | |
|------------------|-------|--------------------|------------|----------|--------------|--------------|--------------|------------|--------------|------------|
| (Proposed PZ | WAS | ATCH-MESA VERDE |) | | | | | | | |
| 43-047-51517 | NBU | 1021-28D4BS BHL | | | | | | | | |
| 43-047-51518 | NBU | 1021-28E4BS BHL | | | | R21E R21E | | | | |
| 43-047-51519 | NBU | 1021-28F4BS BHL | Sec Sec | 28 28 | T10S T10S | R21E R21E | 1736 2163 | FNL FNL | 2232 2153 | FWL FWL |
| NBU 1021-28H PAD | | | | | | | | | | |
| 43-047-51520 | NBU | 1021-28A4BS BHL | | | | R21E R21E | | | | |
| 43-047-51521 | NBU | 1021-28B4BS BHL | | | | R21E R21E | | | | |
| 43-047-51522 | NBU | 1021-28G4BS BHL | | | | R21E R21E | | | | |
| | | 1021-28H4BS BHL | | | | | | | | |
| NBU 1021-29F PAD | | | | | | | | | | |
| 43-047-51524 | NBU | 1021-29C4BS BHL | | | | R21E R21E | | | | |
| 43-047-51525 | NBU | 1021-29D4BS BHL | | | | R21E R21E | | | | |
| 43-047-51526 | NBU | 1021-29E4BS BHL | | | | R21E R21E | | | | |
| | NBU | 1021-29F4BS BHL | | | | R21E R21E | | | | |
| NBU 1021-29I | | | | | | | | | | |
| 43-047-51528 | NBU | 1021-29I1CS BHL | | | | R21E R21E | | | | |
| 43-047-51529 | NBU | 1021-29J1CS BHL | | | | R21E R21E | | | | |
| 43-047-51530 | NBU | 1021-2901CS BHL | | | | R21E R21E | | | | |
| 43-047-51531 | NBU | 1021-29P1CS BHL | | | | R21E R21E | | | | |

Page 3

API # WELL NAME LOCATION

(Proposed PZ WASATCH-MESA VERDE)

NBU 1021-30F

43-047-51532 NBU 1021-30C4BS Sec 30 T10S R21E 1954 FNL 1948 FWL BHL Sec 30 T10S R21E 0826 FNL 2156 FWL 43-047-51533 NBU 1021-30D4BS Sec 30 T10S R21E 1964 FNL 1950 FWL BHL Sec 30 T10S R21E 0821 FNL 0829 FWL 43-047-51534 NBU 1021-30E4BS Sec 30 T10S R21E 1973 FNL 1951 FWL BHL Sec 30 T10S R21E 2136 FNL 0830 FWL 43-047-51535 NBU 1021-30F4BS Sec 30 T10S R21E 1983 FNL 1953 FWL BHL Sec 30 T10S R21E 2150 FNL 2159 FWL 1021-30P PAD 43-047-51536 NBU 1021-30H4BS Sec 30 T10S R21E 1199 FSL 0972 FEL BHL Sec 30 T10S R21E 2175 FNL 0498 FEL 43-047-51537 NBU 1021-30J1CS Sec 30 T10S R21E 1209 FSL 0973 FEL BHL Sec 30 T10S R21E 2162 FSL 1828 FEL

This office has no objection to permitting the wells at this time.

Michael L. Coulthard

Digitally signed by Michael L. Coulthard

DN: cn=Michael L. Coulthard, o=Bureau of Land Management, ou=Branch
of Minerals, email=Michael_Coulthard@blm.gov, c=US
Date: 2011.03.16 12:35:54-06'00'

bcc: File - Natural Buttes Unit Division of Oil Gas and Mining Central Files Agr. Sec. Chron Fluid Chron

MCoulthard:mc:3-16-11

From: Jim Davis

To: Bonner, Ed; Garrison, LaVonne; Hill, Brad; Mason, Diana

CC: Jacobsen, Julie; Lytle, Andy; Piernot, Danielle

Date: 4/28/2011 2:24 PM

Subject: Kerr McGee APD approvals (28)

The following APDs have been approved by SITLA including arch clearance. Paleo clearance is granted with the stipulations noted below.

These wells are approved with out stipulation.

4304751536 NBU 1021-30H4BS 4304751537 NBU 1021-30J1CS 4304751510 NBU 1021-30O4BS 4304751511 NBU 1021-30P1CS 4304751512 NBU 1021-32C4BS 4304751513 NBU 1021-32D4BS 4304751514 NBU 1021-32E4BS 4304751515 NBU 1021-32F4BS

A permitted paleontologist needs to be on-site to observe construction of these wells/ pads.

4304751516 NBU 1021-28C4BS 4304751517 NBU 1021-28D4BS 4304751518 NBU 1021-28E4BS 4304751519 NBU 1021-28F4BS 4304751520 NBU 1021-28A4BS 4304751521 NBU 1021-28B4BS 4304751522 NBU 1021-28G4BS 4304751523 NBU 1021-28H4BS 4304751524 NBU 1021-29C4BS 4304751525 NBU 1021-29D4BS NBU 1021-29E4BS 4304751526 NBU 1021-29F4BS 4304751527 NBU 1021-29I1CS 4304751528 4304751529 NBU 1021-29J1CS NBU 1021-2901CS 4304751530 NBU 1021-29P1CS 4304751531 4304751532 NBU 1021-30C4BS 4304751533 NBU 1021-30D4BS 4304751534 NBU 1021-30E4BS 4304751535 NBU 1021-30F4BS


-Jim Davis

BOPE REVIEW KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 1021-30J1CS 43047515370000

| Sering | Well Name | KERR-MCGEE OIL & GAS ONSHO | | | | SHO | RE, L.P. N | BU | 1021-30J1C | |
|--|---|----------------------------|---------------------------------------|---------------------------|----------------|------|------------|----------------------------|------------|---|
| Setting Depth (TVD) | String | | Surf | Ī | Prod | | | Ī | | |
| Previous Shoe Setting Depth (TVD) | Casing Size(") | | 8.625 | Ī | 4.500 | | | Ī | | |
| Max Mud Weight (ppg) | Setting Depth (TVD) | | 1995 | 9 | 9423 | Ē | | Ī | | |
| ROPE Proposed (psi) | Previous Shoe Setting Dept | th (TVD) | 0 | 1995 | | | | ľ | == | |
| Calculations | Max Mud Weight (ppg) | | 8.3 | | | | | ľ | | |
| Operators Max Anticipated Pressure (psi) | BOPE Proposed (psi) | | 500 | | | | | ľ | | |
| Calculations | Casing Internal Yield (psi) | | 3390 | Ĭ, | 7780 | Ī | | Ī | == | |
| MASP (Fig.) 0.52*Setting Depth*MW Ent. | Operators Max Anticipate | d Pressure (psi) | | H | | | | ľ | | |
| MASP (Pas) 0.52*Setting Depth*MW Ear | Calculations | Sure | f String | | ' | _ | 8 63 | 25 | " | |
| MASP (Gas) (psi) Max BHP-0.12*Setting Depth | | Sun | | ing | Denth*MW | - | | -3 | | |
| MASP (Gas) (psi) Max BHP-(0.12*Setting Depth) G22 Proc. Proc | Will Dill (psi) | | .032 Setti | | , Depui IVI IV | - | 861 | 4 | BOPE Ade | quate For Drilling And Setting Casing at Denth? |
| MASP (Gas/Mud) (psi) Max BHP-(22*Setting Depth = 22 | MASP (Gas) (psi) | Max | x BHP-(0.12* | *Se | etting Depth) | = | 622 | ╡ | | |
| Pressure At Previous Shoe | MASP (Gas/Mud) (psi) | Max | x BHP-(0.22* | *Se | etting Depth) | + | | Ħ | | / |
| Required Casing/BOPE Test Pressure 1995 psi | , , | | · · · · · · · · · · · · · · · · · · · | | | + | <u> </u> | = | <u> </u> | - |
| **Max Pressure Allowed @ Previous Casing Shoe= D | Pressure At Previous Shoe | Max BHP22*(Setting D | epth - Previou | us S | Shoe Depth) | = | 422 | 7 | NO | Reasonable depth in area |
| Calculations | Required Casing/BOPE Te | est Pressure= | | | | T | 1995 | Ħ | psi | |
| Calculations | *Max Pressure Allowed @ | Previous Casing Shoe= | | | | Ti | 0 | Ħ | psi *Assı | ımes 1psi/ft frac gradient |
| Max BHP (psi) | | | | | | | <i></i> | = | | |
| MASP (Gas) (psi) MAS BHP-(0.12*Setting Depth) MASP (Gas/Mud) (psi) MAS BHP-(0.22*Setting Depth) MASP (Gas/Mud) (psi) MAS BHP-22*(Setting Depth - Previous Shoe Depth) MASP (Gas/Mud) (psi) MAX BHP-22*(Setting Depth - Previous Shoe Depth) MASP (Gas/Mud) (psi) MAS BHP-22*(Setting Depth - Previous Shoe Depth) MASP (Gas/Mud) (psi) MAS BHP-22*(Setting Depth - Previous Shoe Depth) MASP (Gas) (psi) MAS BHP (psi) MASP (Gas/Mud) (psi) MAS BHP-(0.12*Setting Depth) MASP (Gas/Mud) (psi) MASP (Fessure At Previous Shoe Max BHP-22*(Setting Depth - Previous Shoe Depth) MASP (Gas/Mud) (psi) MASP (Fessure At Previous Shoe Max BHP-22*(Setting Depth - Previous Shoe Depth) MASP (Gas/Mud) (psi) M | | Proc | | | | | 4.50 | 00 | " | |
| MASP (Gas) (psi) MAX BHP-(0.12*Setting Depth) MAX BHP-(0.22*Setting Depth) MAX Pressure At Previous Shoe MAX BHP-(0.22*Setting Depth) MAX Pressure At Previous Casing Shoe= MAX BHP (psi) MAX BHP (psi) MAX BHP-(0.12*Setting Depth) MAX BHP-(0.22*Setting Depth) MAX BHP-(0.22*Setting Depth) MAX BHP-(0.22*Setting Depth) MAX BHP-(0.22*Setting Depth) MAX Pressure At Previous Shoe MAX BHP-(0.22*Setting Depth) MAX Pressure At Previous Casing Shoe= MAX Pressure At Depth (a) MAX BHP-(0.22*Setting Depth) MAX BHP-(0.22*Setting Depth) MAX BHP-(0.22*Setting Depth) MAX Pressure At Depth (a) MAX BHP-(0.22*Setting Depth) MAX Pressure At Depth (b) MAX BHP-(0.22*Setting Depth) MAX Pressure At Depth (a) MAX BHP-(0.22*Setting Depth) MAX BHP-(0.22 | Max BHP (psi) | | .052*Settii | ing | ig Depth*MW= | | ╝ | | | |
| MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= 4052 | MACD (C.) (°) | | DUD (0.12* | . | P. 41 | - | | _ | | quate For Drilling And Setting Casing at Depth? |
| **Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP-22*(Setting Depth - Previous Shoe Depth) 4491 NO Reasonable Required Casing/BOPE Test Pressure 5000 psi *Max Pressure Allowed @ Previous Casing Shoe= 1995 psi *Assumes lpsi/ft frac gradient **Calculations String " Max BHP (psi) .052*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP-(0.12*Setting Depth) NO Required Casing/BOPE Test Pressure Pressure At Previous Shoe Max BHP-22*(Setting Depth - Previous Shoe Depth) Previous Shoe Depth Previous Shoe Depth Previous Shoe Depth Previous Shoe String Pressure At Previous Shoe Max BHP-22*(Setting Depth String Pressure String Previous Shoe Shoe String Previous Shoe Shoe String Depth Previous Shoe Shoe String Depth Previous Shoe Shoe String Depth Shoe Shoe Shoe Shoe Shoe Shoe Shoe Sho | | | | | | - - | 4994 | ╝ | YES | |
| Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth) Required Casing/BOPE Test Pressure= *Max Pressure Allowed Previous Casing Shoe= *Max Pressure Allowed Previous Casing Shoe= *String Max BHP (psi) .052*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP022*Setting Depth= Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth= *Max Pressure Allowed Previous Casing Shoe= BOPE Adequate For Drilling And Setting Casing at Depth? NO *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Previous Casing Shoe= BOPE Adequate For Drilling And Setting Casing at Depth= psi *Assumes 1psi/ft frac gradient " Galculations String " Max BHP (psi) .052*Setting Depth*MW= Depth= BOPE Adequate For Drilling And Setting Casing at Depth= NO BOPE Adequate For Drilling And Setting Casing at Depth= NO BOPE Adequate For Drilling And Setting Casing at Depth= NO BOPE Adequate For Drilling And Setting Casing at Depth= NO ASP (Gas) (psi) Max BHP (0.12*Setting Depth= NO *Can Full Expected Pressure Be Held At Previous Shoe? NO *Can Full Expected Pressure Be Held At Previous Shoe? *Max Pressure At Previous Shoe *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Press | MASP (Gas/Mud) (psi) | Max | k BHP-(0.22*) | *Se | etting Depth) | = | 4052 | ╝ | t | |
| Required Casing/BOPE Test Pressure= *Max Pressure Allowed @ Previous Casing Shoe= *Max BHP (psi) *Max BHP (psi) *Max BHP-(0.12*Setting Depth*MW= *Can Full Expected Pressure Be Held At Previous Shoe* *Max Pressure At Previous Gasing Shoe= *Max BHP (psi) *Calculations *Can Full Expected Pressure Be Held At Previous Shoe* *Max BHP-(0.12*Setting Depth*MW= *Can Full Expected Pressure Be Held At Previous Shoe* *Max BHP-(0.12*Setting Depth*MW= *Max Pressure At Previous Casing Shoe= *Max Pressure At Previous Casing Shoe= *Max BHP (psi) *Assumes 1psi/ft frac gradient *Assumes 1psi/ft frac gradient *Max BHP (psi) *Assumes 1psi/ft frac gradient *Max BHP (psi) *Max BHP-(0.12*Setting Depth*MW= *BOPE Adequate For Drilling And Setting Casing at Depth? *Max BHP (psi) *Max BHP-(0.12*Setting Depth*MW= *BOPE Adequate For Drilling And Setting Casing at Depth? *Max BHP-(0.22*Setting Depth*MW= *BOPE Adequate For Drilling And Setting Casing at Depth? *Max BHP-(0.22*Setting Depth*MW= *BOPE Adequate For Drilling And Setting Casing at Depth? *Max BHP-(0.22*Setting Depth*MW= *BOPE Adequate For Drilling And Setting Casing at Depth? *Max BHP-(0.22*Setting Depth*MW= *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be He | D A4 D Ch | M DIID 22*/C D | 4h Di | | Ch D4h) | _ | | = | | - |
| *Max Pressure Allowed @ Previous Casing Shoe= 1995 | | | epin - Previou | us i | Snoe Depun) | - - | 4491 | ╛ | | Reasonable |
| Calculations String Max BHP (psi) O52*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP-(0.12*Setting Depth)= NO **Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP-(0.22*Setting Depth)= NO **Assumes 1psi/ft frac gradient BOPE Adequate For Drilling And Setting Casing at Depth? NO **Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Casing Shoe= BOPE Adequate For Drilling And Setting Casing at Depth? NO **Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Casing Shoe= BOPE Adequate For Drilling And Setting Casing at Depth? NO BOPE Adequate For Drilling And Setting Casing at Depth? NO BOPE Adequate For Drilling And Setting Casing at Depth? NO **Assumes 1psi/ft frac gradient BOPE Adequate For Drilling And Setting Casing at Depth? NO **Assumes 1psi/ft frac gradient **Assumes 1psi/ft frac | | | | _ | | 4 | 5000 | ╛ | • | 1 1/0 0 |
| Max BHP (psi) .052*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP-(0.12*Setting Depth)= MASP (Gas/Mud) (psi) Max BHP02.2*Setting Depth - Previous Shoe Depth)= **Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe **Assumes 1psi/ft frac gradient Calculations String " Max BHP (psi) Max BHP (psi) Max BHP0.22*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? NO BOPE Adequate For Drilling And Setting Casing at Depth? NO BOPE Adequate For Drilling And Setting Casing at Depth? NO BOPE Adequate For Drilling And Setting Casing at Depth? NO BOPE Adequate For Drilling And Setting Casing at Depth? NO BOPE Adequate For Drilling And Setting Casing at Depth? NO ASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= MASP (Gas/Mud) (psi) Max BHP22*(Setting Depth - Previous Shoe Depth)= **Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= | *Max Pressure Allowed (a) | Previous Casing Shoe= | | | | | 1995 | Ш | psi *Assi | imes Tpsi/ft frac gradient |
| BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP-(0.12*Setting Depth) NO NO | Calculations | S | tring | | | Т | | | " | |
| MASP (Gas) (psi) MAX BHP-(0.12*Setting Depth)= MASP (Gas/Mud) (psi) MAX BHP-(0.22*Setting Depth)= *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe MAX BHP22*(Setting Depth - Previous Shoe Depth)= *Max Pressure Allowed @ Previous Casing Shoe= *Max Pressure Allowed @ Previous Casing Shoe= *String " Max BHP (psi) .052*Setting Depth*MW= MASP (Gas) (psi) Max BHP-(0.12*Setting Depth)= MASP (Gas) (psi) Max BHP-(0.22*Setting Depth)= MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= MASP (Gas/Mud) (psi) Max BHP22*(Setting Depth - Previous Shoe Depth)= Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= NO *Can Full Expected Pressure Be Held At Previous Shoe? *Can Full Expected Pressure Be Held At Previous Shoe? NO *Can Full Expected Pressure Be Held At Previous Shoe? NO *Can Full Expected Pressure Be Held At Previous Shoe? NO *Can Full Expected Pressure Be Held At Previous Shoe? | Max BHP (psi) | | .052*Settii | ing | Depth*MW | | | 3 | | |
| MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= *Max Pressure Allowed @ Previous Casing Shoe= *Max Pressure Allowed @ Previous Casing Shoe= *In the state of the st | | | | | | | | | BOPE Ade | quate For Drilling And Setting Casing at Depth? |
| *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= | MASP (Gas) (psi) | Max | x BHP-(0.12* | *Se | etting Depth) | = [| a. | _ | NO | |
| Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth) | MASP (Gas/Mud) (psi) | Max | x BHP-(0.22* | *Se | etting Depth) | = [| | | NO | |
| Required Casing/BOPE Test Pressure= *Max Pressure Allowed @ Previous Casing Shoe= psi *Assumes 1psi/ft frac gradient Calculations String " | | | | | | | | | *Can Full | Expected Pressure Be Held At Previous Shoe? |
| *Max Pressure Allowed @ Previous Casing Shoe= psi *Assumes 1psi/ft frac gradient Calculations String | Pressure At Previous Shoe | Max BHP22*(Setting D | epth - Previou | us S | Shoe Depth) | = [| | | NO | |
| Calculations String Max BHP (psi) .052*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP-(0.12*Setting Depth)= MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= | Required Casing/BOPE Te | est Pressure= | | | | | | | psi | |
| Max BHP (psi) .052*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP-(0.12*Setting Depth)= MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= | *Max Pressure Allowed @ Previous Casing Shoe= | | | | | | psi *Assı | umes 1psi/ft frac gradient | | |
| Max BHP (psi) .052*Setting Depth*MW= BOPE Adequate For Drilling And Setting Casing at Depth? MASP (Gas) (psi) Max BHP-(0.12*Setting Depth)= MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= | Calculations | S | tring | _ | | Т | | | " | |
| MASP (Gas) (psi) Max BHP-(0.12*Setting Depth)= NO MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= NO *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= NO NO *Can Full Expected Pressure Be Held At Previous Shoe? | Max BHP (psi) | | 5 | | - | | ╗ | | | |
| MASP (Gas/Mud) (psi) Max BHP-(0.22*Setting Depth)= *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= NO | | | | | | 1 | | | BOPE Ade | quate For Drilling And Setting Casing at Depth? |
| *Can Full Expected Pressure Be Held At Previous Shoe? Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= | MASP (Gas) (psi) | Max | x BHP-(0.12* | BHP-(0.12*Setting Depth)= | | | | _ | NO | |
| Pressure At Previous Shoe Max BHP22*(Setting Depth - Previous Shoe Depth)= | MASP (Gas/Mud) (psi) | Max | x BHP-(0.22* | *Se | etting Depth) | = | | j | NO | |
| | | | | | | ľ | | | *Can Full | Expected Pressure Be Held At Previous Shoe? |
| Required Casing/BOPE Test Pressure= psi | Pressure At Previous Shoe | Max BHP22*(Setting D | epth - Previou | us S | Shoe Depth) | = | | | NO | |
| | Required Casing/BOPE Te | est Pressure= | | | | T | | 7 | psi | |

*Max Pressure Allowed @ Previous Casing Shoe= psi *Assumes 1psi/ft frac gradient

43047515370000 NBU 1021-30J1CS



Well name:

43047515370000 NBU 1021-30J1CS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Surface

Project ID:

43-047-51537

Location:

UINTAH

COUNTY

Minimum design factors: **Environment:**

Collapse

8.600 ppg Mud weight: Design is based on evacuated pipe.

Collapse:

Design factor 1.125

H2S considered? No 74 °F Surface temperature: 102 °F

Bottom hole temperature: 1.40 °F/100ft Temperature gradient:

100 ft Minimum section length:

Burst:

1.00 Design factor

Cement top:

972 ft

Burst

Max anticipated surface

pressure:

Design parameters:

1,101 psi

Internal gradient: Calculated BHP

0.120 psi/ft

1,340 psi

No backup mud specified.

Body yield:

Tension:

8 Round STC:

1.80 (J) 1.70 (J) 8 Round LTC: Buttress: 1.60 (J) Premium: 1.50 (J)

1.50 (B)

Tension is based on air weight. Neutral point: 1,803 ft Directional Info - Build & Drop

Kick-off point 300 ft Departure at shoe: 483 ft

Maximum dogleg: 2 °/100ft

23.95° Inclination at shoe:

Re subsequent strings: Next setting depth:

2,080 ft Next mud weight: 12.500 ppg Next setting BHP: 1,351 psi Fracture mud wt: 19.250 ppg

Fracture depth: Injection pressure:

2,080 ft 2,080 psi

| | (ft) | (in) | (lbs/ft) | | Finish | Depth (ft) | Depth (ft) | Diameter (in) | Cost (\$) |
|-----|------|---------------------------------------|---------------------------------------|--------------------------------|------------------------------------|-----------------------------------|-----------------------------------|--------------------------------------|---------------------------------------|
| 1 : | 2080 | 8.625 | 28.00 | 1-55 | LT&C | 1995 | 2080 | 7.892 | 82368 |
| - | | Collapse Strength (psi) 1880 | Collapse Design Factor 2.109 | Burst Load (psi) 1340 | Burst Strength (psi) 3390 | Burst Design Factor 2.53 | Tension Load (kips) 55.9 | Tension Strength (kips) 348 | Tension Design Factor 6.23 J |

Prepared

by:

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357

FAX: 801-359-3940

Date: May 17,2011 Salt Lake City, Utah

Collapse is based on a vertical depth of 1995 ft, a mud weight of 8.6 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Well name:

43047515370000 NBU 1021-30J1CS

Operator:

KERR-MCGEE OIL & GAS ONSHORE, L.P.

String type:

Production

Project ID: 43-047-51537

Location:

UINTAH

COUNTY

Collapse

Mud weight: Internal fluid density:

Design parameters:

12.500 ppg 1,000 ppg

Minimum design factors: Collapse:

Design factor

Environment: 1.125

H2S considered? Surface temperature: Bottom hole temperature:

No 74 °F 206 °F

Temperature gradient: Minimum section length: 1.40 °F/100ft

100 ft

Burst:

Design factor

1.00

Cement top:

1,994 ft

Burst

Max anticipated surface pressure:

Internal gradient: Calculated BHP

4,046 psi 0.220 psi/ft 6,119 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J) 8 Round LTC: 1.80 (J) 1.60 (J) Buttress:

Premium: Body yield:

1.50 (J) 1.60 (B) Directional Info - Build & Drop

Kick-off point 300 ft Departure at shoe: 1298 ft Maximum dogleg: 2 °/100ft

Inclination at shoe:

0 °

Tension is based on air weight.

Neutral point:

7,899 ft

| Run | Segment | | Nominal | | End | True Vert | Measured | Drift | Est. |
|-----|-------------------|----------------|--------------------|---------------|-------------------|------------------|----------------|--------------------|------------------|
| Seq | Length (ft) | Size (in) | Weight (lbs/ft) | Grade | Finish | Depth (ft) | Depth (ft) | Diameter (in) | Cost (\$) |
| 1 | 9660 | 4.5 | 11.60 | I-80 | LT&C | 9423 | 9660 | 3.875 | 127512 |
| Run | Collapse | Collapse | Collapse | Burst | Burst | Burst | Tension | Tension | Tension |
| Seq | Load (psi) | Strength (psi) | Design Factor | Load (psi) | Strength (psi) | Design Factor | Load (kips) | Strength (kips) | Design Factor |
| 1 | 5629 [°] | 6360 | 1.130 | 6119 | 7780 | 1.27 | 109.3 | 212 | 1.94 J |

Prepared

by:

Helen Sadik-Macdonald

Div of Oil, Gas & Mining

Phone: 801 538-5357 FAX: 801-359-3940

Date: May 17,2011 Salt Lake City, Utah

Collapse is based on a vertical depth of 9423 ft, a mud weight of 12.5 ppg An internal gradient of .052 psi/ft was used for collapse from TD Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

Engineering responsibility for use of this design will be that of the purchaser,

ON-SITE PREDRILL EVALUATION

Utah Division of Oil, Gas and Mining

Operator KERR-MCGEE OIL & GAS ONSHORE, L.P.

Well Name NBU 1021-30J1CS

API Number 43047515370000 APD No 3554 Field/Unit NATURAL BUTTES

Location: 1/4,1/4 SESE **Sec** 30 **Tw** 10.0S **Rng** 21.0E 1209 FSL 973 FEL

GPS Coord (UTM) 620702 4419024 Surface Owner

Participants

See other comments.

Regional/Local Setting & Topography

The general area is within the Natural Buttes Unit in the middle portion of the Cottonwood Wash Drainage of Uintah County. The area is characterized by rolling hills and benches which are frequently intersected by somewhat gentle draws. The draws are occasionally rimed with steep side hills which have exposed sand stone bedrock cliffs along the rims. Cottonwood Wash is an ephemeral drainage, which drains northerly approximately 5 miles to the White River. No seeps, springs or streams exist in the area. An occasional pond, constructed to store runoff for cattle and livestock exists.

This location is approximately 17.8 road miles south of Ouray, Utah and 48 road miles southwest of Vernal, Utah. It is accessed by the Seep Ridge Road then by Uintah County and existing oil field development roads to the existing location.

The proposed NBU 1021-30P pad will contain 4 gas wells all to be directionally drilled. They are the NBU 1021-30J1CS, NBU 1021-30H4BS, NBU 1021-30P1CS and NBU 1021-30O4BS. The location is oriented in a south to north direction on the existing pad of the shut-in NBU 390 gas well. The pad will be extended in all directions with only a small fill to the north. The site is limited on the west by a shallow but well defined draw and on the north by a similar drainage. A drainage diversion is needed as shown around corner 10 and needs to begin on the east side of the pad near corner 1. Corner 10 should also be rounded. Between corners 2 and 3 an active drainage enters the site. It will be blocked with spoils forming a berm directing the flow to the east of a knoll while drilling. When the site is reclaimed it can be moved back to near its existing location. Maximum cut for the pad is 5.8 feet at location corner 2 and maximum fill is 4.9 feet at corner 10. A secondary drainage of Cottonwood Wash is a short distance to the west.

The selected location appears to be a suitable site for drilling and operating a well, and is the best site in the immediate area

Both the surface and minerals for this location are owned by SITLA.

Surface Use Plan

Current Surface Use

Grazing Recreational Wildlfe Habitat

New Road Miles Well Pad Src Const Material Surface Formation

0 Width 353 Length 455 Onsite UNTA

Ancillary Facilities N

5/19/2011 Page 1

Waste Management Plan Adequate?

Environmental Parameters

Affected Floodplains and/or Wetlands N

Flora / Fauna

Vegetation is a desert shrub type. Vegetation included shadscale, tamarix, broom snakeweed, sagebrush, curly mesquite grass, annual mustard, mat saltbrush, squirrel tail, cheat grass, prickly pear and spring annuals.

Antelope, cattle, rabbits, covotes, and small mammals, birds and raptors.

Soil Type and Characteristics

Shallow rocky sandy loam.

Erosion Issues N

Sedimentation Issues Y

Site Stability Issues N

Drainage Diverson Required? Y

Berm Required? N

Erosion Sedimentation Control Required? Y

See other comments.

Paleo Survey Run? Y Paleo Potental Observed? N Cultural Survey Run? Y Cultural Resources?

Reserve Pit

| Site-Specific Factors | Site R | anking | |
|---|------------------|--------|---------------------|
| Distance to Groundwater (feet) | 100 to 200 | 5 | |
| Distance to Surface Water (feet) | >1000 | 0 | |
| Dist. Nearest Municipal Well (ft) | >5280 | 0 | |
| Distance to Other Wells (feet) | | 20 | |
| Native Soil Type | Mod permeability | 10 | |
| Fluid Type | Fresh Water | 5 | |
| Drill Cuttings | Normal Rock | 0 | |
| Annual Precipitation (inches) | | 0 | |
| Affected Populations | | | |
| Presence Nearby Utility Conduits | Not Present | 0 | |
| | Final Score | 40 | 1 Sensitivity Level |

Characteristics / Requirements

The reserve pit is planned in an area of cut in the southwest corner of the location. Dimensions are 100' x 260' x 12' deep with 2' of freeboard and a 15' outer bench. Kerr McGee proposed to line the pit with a 30-mil liner and 2 layers of felt.

Closed Loop Mud Required? N Liner Required? Y Liner Thickness 30 Pit Underlayment Required? Y

5/19/2011 Page 2

Other Observations / Comments

Floyd Bartlett (DOGM), Jim Davis (SITLA), Clay Einerson, Charles Chase, Roger Perry, Duane Holmes, Kenny Gathings, Andy Lytle and Shelia Wopsock (Kerr McGee), Alex Hansen and Ben Williams (UDWR), Mitch Batty, John Slaugh, (Timberline Engineering and Land Surveying).

. A drainage diversion is needed as shown around corner 10 and needs to begin on the east side of the pad near corner 1. Corner 10 should also be rounded. Between corners 2 and 3 an active drainage enters the site. It will be blocked with spoils forming a berm directing the flow to the east of a knoll while drilling. When the site is reclaimed it can be moved back to near its existing location.

Floyd Bartlett **Evaluator**

3/30/2011

Date / Time

5/19/2011 Page 3

Application for Permit to Drill Statement of Basis

Utah Division of Oil, Gas and Mining

Page 1

| APD No | API WellNo | Status | Well Type | Surf Owner | CBM |
|-----------|--------------------------|------------|--------------------------|-------------------|------------|
| 3554 | 43047515370000 | SITLA | GW | S | No |
| Operator | KERR-MCGEE OIL & GAS ONS | HORE, L.P. | Surface Owner-APD | | |
| Well Name | NBU 1021-30J1CS | | Unit | NATURAL B | UTTES |
| Field | NATURAL BUTTES | | Type of Work | DRILL | |
| Location | SESE 30 10S 21E S 1209 | FSL 973 FE | L GPS Coord (UTM) | 620696E 4419 | 9036N |
| | | | | | |

Geologic Statement of Basis

5/19/2011

Kerr McGee proposes to set 2,080' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 4,150'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 30. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought up above the base of the moderately saline ground water to isolate it from fresher waters uphole.

Brad Hill 4/26/2011
APD Evaluator Date / Time

Surface Statement of Basis

The general area is within the Natural Buttes Unit in the middle portion of the Cottonwood Wash Drainage of Uintah County. The area is characterized by rolling hills and benches which are frequently intersected by somewhat gentle draws. The draws are occasionally rimed with steep side hills which have exposed sand stone bedrock cliffs along the rims. Cottonwood Wash is an ephemeral drainage, which drains northerly approximately 5 miles to the White River. No seeps, springs or streams exist in the area. An occasional pond, constructed to store runoff for cattle and livestock exists.

This location is approximately 17.8 road miles south of Ouray, Utah and 48 road miles southwest of Vernal, Utah. It is accessed by the Seep Ridge Road then by Uintah County and existing oil field development roads to the existing location.

The proposed NBU 1021-30P pad will contain 4 gas wells all to be directionally drilled. They are the NBU 1021-30J1CS, NBU 1021-30H4BS, NBU 1021-30P1CS and NBU 1021-30O4BS. The location is oriented in a south to north direction on the existing pad of the shut-in NBU 390 gas well. The pad will be extended in all directions with only a small fill to the north. The site is limited on the west by a shallow but well defined draw and on the north by a similar drainage. A drainage diversion is needed as shown around corner 10 and needs to begin on the east side of the pad near corner 1. Corner 10 should also be rounded. Between corners 2 and 3 an active drainage enters the site. It will be blocked with spoils forming a berm directing the flow to the east of a knoll while drilling. When the site is reclaimed it can be moved back to near its existing location. Maximum cut for the pad is 5.8 feet at location corner 2 and maximum fill is 4.9 feet at corner 10. A secondary drainage of Cottonwood Wash is a short distance to the west.

The selected location appears to be a suitable site for drilling and operating a well, and is the best site in the immediate area

Both the surface and minerals for this location are owned by SITLA. Jim Davis of SITLA attended the site visit. He had no concerns regarding the proposal except as noted above. A seed mix to be used in reclamation has previously been provided to Kerr McGee by SITLA for this zone. Ben Williams and Alex Hansen of the

Application for Permit to Drill Statement of Basis

Utah Division of Oil, Gas and Mining

Page 2

UDWR also attended. The area is classified as yearlong crucial habitat for antelope but no restrictions were recommended. No other wildlife species are expected to be significantly affected.

Floyd Bartlett 3/30/2011
Onsite Evaluator Date / Time

Conditions of Approval / Application for Permit to Drill

Category Condition

5/19/2011

Pits A synthetic liner with a minimum thickness of 30 mils with a double felt subliner shall be properly installed and

maintained in the reserve pit.

Surface Drainages adjacent to the proposed pad shall be diverted around the location. Surface The reserve pit shall be fenced upon completion of drilling operations.

WORKSHEET APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 3/11/2011 **API NO. ASSIGNED:** 43047515370000

WELL NAME: NBU 1021-30J1CS

OPERATOR: KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995) **PHONE NUMBER:** 720 929-6156

CONTACT: Danielle Piernot

PROPOSED LOCATION: SESE 30 100S 210E **Permit Tech Review:**

> **SURFACE: 1209 FSL 0973 FEL Engineering Review:**

BOTTOM: 2162 FSL 1828 FEL Geology Review:

COUNTY: UINTAH

LATITUDE: 39.91471 LONGITUDE: -109.58785

UTM SURF EASTINGS: 620696.00 NORTHINGS: 4419036.00

FIELD NAME: NATURAL BUTTES

LEASE TYPE: 3 - State

LEASE NUMBER: ML 22793 PROPOSED PRODUCING FORMATION(S): WASATCH-MESA VERDE

SURFACE OWNER: 3 - State COALBED METHANE: NO

RECEIVED AND/OR REVIEWED: LOCATION AND SITING:

 PLAT R649-2-3.

Unit: NATURAL BUTTES **Bond:** STATE/FEE - 22013542

Potash R649-3-2. General

Oil Shale 190-5

Oil Shale 190-3 R649-3-3. Exception

Drilling Unit Oil Shale 190-13

Board Cause No: Cause 173-14 Water Permit: Permit #43-8496

Effective Date: 12/2/1999 **RDCC Review:**

Siting: Suspends General Siting **Fee Surface Agreement**

✓ Intent to Commingle R649-3-11. Directional Drill

Commingling Approved

Comments: Presite Completed

Stipulations:

3 - Commingling - ddoucet 5 - Statement of Basis - bhill 12 - Cement Volume (3) - ddoucet 15 - Directional - dmason 17 - Oil Shale 190-5(b) - dmason 25 - Surface Casing - hmacdonald

API Well No: 43047515370000



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA
Division Director

Permit To Drill

Well Name: NBU 1021-30J1CS **API Well Number:** 43047515370000

Lease Number: ML 22793 **Surface Owner:** STATE **Approval Date:** 5/19/2011

Issued to:

KERR-MCGEE OIL & GAS ONSHORE, L.P., P.O. Box 173779, Denver, CO 80217

Authority:

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14. The expected producing formation or pool is the WASATCH-MESA VERDE Formation(s), completion into any other zones will require filing a Sundry Notice (Form 9). Completion and commingling of more than one pool will require approval in accordance with R649-3-22.

Duration:

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

Commingle:

In accordance with Board Cause No. 173-14, commingling of the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

General:

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

Conditions of Approval:

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

API Well No: 43047515370000

Cement volume for the 4 1/2" production string shall be determined from actual hole diameter in order to place cement from the pipe setting depth back to 1880' MD minimum.

Additional Approvals:

The operator is required to obtain approval from the Division of Oil, Gas and mining before performing any of the following actions during the drilling of this well:

- Any changes to the approved drilling plan contact Dustin Doucet
- Significant plug back of the well contact Dustin Doucet
- Plug and abandonment of the well contact Dustin Doucet

Notification Requirements:

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- Within 24 hours following the spudding of the well contact Carol Daniels OR
- submit an electronic sundry notice (pre-registration required) via the Utah Oil & Gas website at http://oilgas.ogm.utah.gov
- 24 hours prior to testing blowout prevention equipment contact Dan Jarvis
- 24 hours prior to cementing or testing casing contact Dan Jarvis
- Within 24 hours of making any emergency changes to the approved drilling program contact Dustin Doucet
- 24 hours prior to commencing operations to plug and abandon the well contact Dan Jarvis

Contact Information:

The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voicemail message if the person is not available to take the call):

- Carol Daniels 801-538-5284 office
- Dustin Doucet 801-538-5281 office

801-733-0983 - after office hours

• Dan Jarvis 801-538-5338 - office

801-231-8956 - after office hours

Reporting Requirements:

All reports, forms and submittals as required by the Utah Oil and Gas Conservation General Rules will be promptly filed with the Division of Oil, Gas and Mining, including but not limited to:

- Entity Action Form (Form 6) due within 5 days of spudding the well
- Monthly Status Report (Form 9) due by 5th day of the following calendar month
- Requests to Change Plans (Form 9) due prior to implementation
- Written Notice of Emergency Changes (Form 9) due within 5 days
- Notice of Operations Suspension or Resumption (Form 9) due prior to implementation
- Report of Water Encountered (Form 7) due within 30 days after completion
- Well Completion Report (Form 8) due within 30 days after completion or plugging

Annuariad Drie

API Well No: 43047515370000

Approved by:

For John Rogers Associate Director, Oil & Gas Sundry Number: 25752 API Well Number: 43047515370000

| | | | FORM 9 | | | | |
|--|---|---|---|--|--|--|--|
| | STATE OF UTAH | | FORM 9 | | | | |
| | DEPARTMENT OF NATURAL RESOURC DIVISION OF OIL, GAS, AND MIN | | 5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22793 | | | | |
| SUNDF | ON WELLS | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: | | | | | |
| | oposals to drill new wells, significantly or reenter plugged wells, or to drill horizon n for such proposals. | | 7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES | | | | |
| 1. TYPE OF WELL Gas Well | | 8. WELL NAME and NUMBER: NBU 1021-30J1CS | | | | | |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON | NSHORE, L.P. | | 9. API NUMBER: 43047515370000 | | | | |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18t | h Street, Suite 600, Denver, CO, 80217 | PHONE NUMBER: 720 929- | 9. FIELD and POOL or WILDCAT: 5NIATURAL BUTTES | | | | |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1209 FSL 0973 FEL | | | COUNTY: UINTAH | | | | |
| QTR/QTR, SECTION, TOWNS | HIP, RANGE, MERIDIAN: 0 Township: 10.0S Range: 21.0E Meridi | an: S | STATE: UTAH | | | | |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | | | | | | |
| TYPE OF SUBMISSION | | TYPE OF ACTION | | | | | |
| | ACIDIZE | ALTER CASING | CASING REPAIR | | | | |
| NOTICE OF INTENT Approximate date work will start: | CHANGE TO PREVIOUS PLANS | CHANGE TUBING | CHANGE WELL NAME | | | | |
| 5/19/2012 | CHANGE WELL STATUS | COMMINGLE PRODUCING FORMATIONS | CONVERT WELL TYPE | | | | |
| | | | | | | | |
| SUBSEQUENT REPORT Date of Work Completion: | DEEPEN | FRACTURE TREAT | ☐ NEW CONSTRUCTION | | | | |
| | OPERATOR CHANGE | PLUG AND ABANDON | PLUG BACK | | | | |
| SPUD REPORT | PRODUCTION START OR RESUME | RECLAMATION OF WELL SITE | RECOMPLETE DIFFERENT FORMATION | | | | |
| Date of Spud: | REPERFORATE CURRENT FORMATION | SIDETRACK TO REPAIR WELL | TEMPORARY ABANDON | | | | |
| | TUBING REPAIR | VENT OR FLARE | WATER DISPOSAL | | | | |
| DRILLING REPORT | WATER SHUTOFF | SI TA STATUS EXTENSION | ✓ APD EXTENSION | | | | |
| Report Date: | WILDCAT WELL DETERMINATION | OTHER | OTHER: | | | | |
| 40 DECORIDE PROPOSED OR | | di sentiment detelle includio e detec | <u>'</u> | | | | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to this APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you. Approved by the Utah Division of Oil, Gas and Mining | | | | | | | |
| | | | Date: May 21, 2012 | | | | |
| | | | By: Bacylll | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| NAME (PLEASE PRINT) Danielle Piernot | PHONE NUMB 720 929-6156 | ER TITLE Regulatory Analyst | | | | | |
| SIGNATURE N/A | | DATE 5/15/2012 | | | | | |

Sundry Number: 25752 API Well Number: 43047515370000



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047515370000

API: 43047515370000 Well Name: NBU 1021-30J1CS

Location: 1209 FSL 0973 FEL QTR SESE SEC 30 TWNP 100S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 5/19/2011

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

| - mig is a silicomo or como nomo relator to ano approvation, initiati en como ano ano ano ano ano ano ano ano a |
|--|
| • If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No |
| Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No |
| Has there been any unit or other agreements put in place that could affect the permitting or operation of this proposed well? Yes No |
| Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? Yes No |
| • Has the approved source of water for drilling changed? Yes No |
| Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No |
| • Is bonding still in place, which covers this proposed well? Yes No |
| nature: Danielle Piernot Date: 5/15/2012 |

Sig

Title: Regulatory Analyst Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Sundry Number: 37796 API Well Number: 43047515370000

| | | | FORM 9 | | | | |
|---|---|---------------------------------------|---|--|--|--|--|
| | STATE OF UTAH | | POKIM 9 | | | | |
| , | DEPARTMENT OF NATURAL RESOURCE DIVISION OF OIL, GAS, AND MIN | | 5.LEASE DESIGNATION AND SERIAL NUMBER: ML 22793 | | | | |
| SUNDR | ON WELLS | 6. IF INDIAN, ALLOTTEE OR TRIBE NAME: | | | | | |
| | oposals to drill new wells, significantly or reenter plugged wells, or to drill horizor n for such proposals. | | 7.UNIT or CA AGREEMENT NAME: NATURAL BUTTES | | | | |
| 1. TYPE OF WELL Gas Well | 8. WELL NAME and NUMBER: NBU 1021-30J1CS | | | | | | |
| 2. NAME OF OPERATOR: KERR-MCGEE OIL & GAS ON | NSHORE, L.P. | | 9. API NUMBER: 43047515370000 | | | | |
| 3. ADDRESS OF OPERATOR: P.O. Box 173779 1099 18tl | h Street, Suite 600, Denver, CO, 80217 | PHONE NUMBER: 3779 720 929-6 | 9. FIELD and POOL or WILDCAT: 65NATURAL BUTTES | | | | |
| 4. LOCATION OF WELL FOOTAGES AT SURFACE: 1209 FSL 0973 FEL | | | COUNTY: UINTAH | | | | |
| QTR/QTR, SECTION, TOWNSH | HIP, RANGE, MERIDIAN: 0 Township: 10.0S Range: 21.0E Meridia | nn: S | STATE: UTAH | | | | |
| 11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA | | | | | | | |
| TYPE OF SUBMISSION | | TYPE OF ACTION | | | | | |
| | ACIDIZE | ALTER CASING | CASING REPAIR | | | | |
| NOTICE OF INTENT Approximate date work will start: | CHANGE TO PREVIOUS PLANS | CHANGE TUBING | CHANGE WELL NAME | | | | |
| 5/19/2013 | CHANGE WELL STATUS | COMMINGLE PRODUCING FORMATIONS | CONVERT WELL TYPE | | | | |
| | | | | | | | |
| SUBSEQUENT REPORT Date of Work Completion: | DEEPEN | FRACTURE TREAT | ☐ NEW CONSTRUCTION | | | | |
| | OPERATOR CHANGE | PLUG AND ABANDON | PLUG BACK | | | | |
| SPUD REPORT | PRODUCTION START OR RESUME | RECLAMATION OF WELL SITE | RECOMPLETE DIFFERENT FORMATION | | | | |
| Date of Spud: | REPERFORATE CURRENT FORMATION | SIDETRACK TO REPAIR WELL | TEMPORARY ABANDON | | | | |
| | TUBING REPAIR | VENT OR FLARE | WATER DISPOSAL | | | | |
| DRILLING REPORT | WATER SHUTOFF | SI TA STATUS EXTENSION | ✓ APD EXTENSION | | | | |
| Report Date: | WILDCAT WELL DETERMINATION | OTHER | OTHER: | | | | |
| 40 DECORIDE PROPOSED OR | | U | · <u> </u> | | | | |
| 12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. Kerr-McGee Oil & Gas Onshore, L.P. (Kerr-McGee) respectfully requests an extension to the APD for the maximum time allowed. Please contact the undersigned with any questions and/or comments. Thank you. Approved by the Utah Division of Oil, Gas and Mining | | | | | | | |
| | | | Date: May 14, 2013 | | | | |
| | | | By: Laggill | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| NAME (PLEASE PRINT) Teena Paulo | PHONE NUMBE 720 929-6236 | ER TITLE Staff Regulatory Specialist | | | | | |
| SIGNATURE | | DATE | | | | | |
| N/A | | 5/10/2013 | | | | | |

Sundry Number: 37796 API Well Number: 43047515370000



The Utah Division of Oil, Gas, and Mining

- State of Utah
- Department of Natural Resources

Electronic Permitting System - Sundry Notices

Request for Permit Extension Validation Well Number 43047515370000

API: 43047515370000 Well Name: NBU 1021-30J1CS

Location: 1209 FSL 0973 FEL QTR SESE SEC 30 TWNP 100S RNG 210E MER S

Company Permit Issued to: KERR-MCGEE OIL & GAS ONSHORE, L.P.

Date Original Permit Issued: 5/19/2011

The undersigned as owner with legal rights to drill on the property as permitted above, hereby verifies that the information as submitted in the previously approved application to drill, remains valid and does not require revision. Following is a checklist of some items related to the application, which should be verified.

| • If located on private land, has the ownership changed, if so, has the surface agreement been updated? Yes No |
|--|
| Have any wells been drilled in the vicinity of the proposed well which would affect the spacing or siting requirements for this location? Yes No |
| • Has there been any unit or other agreements put in place that could affect the permitting or operation of thi proposed well? Yes No |
| • Have there been any changes to the access route including ownership, or rightof- way, which could affect the proposed location? (Yes (No |
| • Has the approved source of water for drilling changed? Yes No |
| • Have there been any physical changes to the surface location or access route which will require a change in plans from what was discussed at the onsite evaluation? Yes No |
| • Is bonding still in place, which covers this proposed well? Yes No |
| nature: Teena Paulo Date: 5/10/2013 |

Sig

Title: Staff Regulatory Specialist Representing: KERR-MCGEE OIL & GAS ONSHORE, L.P.



Kerr-McGee APDs to Rescind

Paulo, Teena <Teena.Paulo@anadarko.com>
To: "dianawhitney@utah.gov" <dianawhitney@utah.gov>

Mon, Apr 14, 2014 at 7:48 AM

Good Morning Diana,

Please see the below list of wells for the APD's that Kerr-McGee requests to rescind with UDOGM.

| Well Name | API Number |
|-----------------|------------|
| NBU 1021-28F4BS | 4304751519 |
| NBU 1021-28E4BS | 4304751518 |
| NBU 1021-28D4BS | 4304751517 |
| NBU 1021-28C4BS | 4304751516 |
| NBU 1021-30P1CS | 4304751511 |
| NBU 1021-30O4BS | 4304751510 |
| NBU 1021-30J1CS | 4304751537 |
| NBU 1021-30H4BS | 4304751536 |
| NBU 1021-32F4BS | 4304751515 |
| NBU 1021-32D4BS | 4304751513 |
| NBU 1021-32C4BS | 4304751512 |
| NBU 1021-32E4BS | 4304751514 |
| NBU 921-22C GR | 4304752559 |

Thank you,

Teena Paulo Staff Regulatory Specialist Anadarko Petroleum 1099 18th Street, Suite 600 Denver, CO 80202

Click here for Anadarko's Electronic Mail Disclaimer



State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas and Mining

JOHN R. BAZA

Division Director

April 22, 2014

Teena Paulo Kerr-McGee Oil & Gas Onshore, LP 1099 18th Street, Suite 600 Denver, CO 80202

Re: APDs Rescinded for Kerr-McGee O&G Onshore, L.P., Uintah County

Dear Ms. Paulo:

Enclosed find the list of APDs that you have asked to be rescinded. No drilling activity at these locations has been reported to the division. Therefore, approval to drill these wells is hereby rescinded, effective April 14, 2014.

A new APD must be filed with this office for approval <u>prior</u> to the commencement of any future work on the subject location.

If any previously unreported operations have been performed on this well location, it is imperative that you notify the Division immediately.

Sincerely,

Diana Mason

Environmental Scientist

ionellasm

cc:

Well File

Bureau of Land Management, Vernal



| NBU 1021-28F4BS |
|-----------------------|
| NBU 1021-28E4BS |
| NBU 1021-28D4BS |
| NBU 1021-28C4BS |
| NBU 1021-30P1CS |
| NBU 1021-30O4BS |
| NBU 1021-30J1CS |
| NBU 1021-30H4BS |
| NBU 1021-32F4BS |
| NBU 1021-32D4BS |
| NBU 1021-32C4BS |
| NBU 1021-32E4BS |
| NBU 921-22C GR |
| |